

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry

(County)

Located In:

Corner Code #4

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-----------|
| 1. Public Land Survey | T | <u>3W</u> | R | <u>10W</u> | <u>X4</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11	●	12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary C. Bilow, in a field survey on April 01, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

#4: Post established by U.S. Deputy Surveyor S. Sibley in 1831 - accessories: W. Oak 8 S42W 29 links & W. Oak 8 N31W 110 links. No other records found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

#4: Reestablished corner at the intersection of an East - West fence line and a 33' offset line from the treeline running North along the East R.O.W. of Yankee Springs Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

#4: Set 1/2" rebar with plastic cap stamped "G.C. Bilow LLS 26453" in Monument box in centerline road
 East 32.19', Nail & Tag in 29" Oak
 N26E 71.43', Nail & Tag in 32" Oak
 N85W 48.13', Nail & Tag in 19" Oak
 S47W 63.11', Nail & Tag in 7" Oak



Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 8/31/93