

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Barry
(County)

	Located In:	Corner Code \neq
1. Public Land Survey	T <u>3N</u> R <u>10W</u>	<u>15</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Gary C. Bilow, in a field survey on April 01, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration.
 15: Post established by U.S. Deputy Surveyor S. Sibley in 1831 - accessories: W. Oak 20 N35E 4.5 links & B. Oak 8 N42W 10 links.
 County Surveyor J. Greasy recorded in 1874 "Commenced survey of Section 10 T3N R10W at Section Corner Secs 10, 11, 14 & 15 - Took new bearings - W. Oak 16 N89W 1.55 links. B. Oak 12 N45E 0.21 links."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 15: Reestablished corner at intersection of North - South fenceline and the split of the right of way fences along Bowens Mill Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 15: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast Aluminum Michigan Department of Natural Resources Tablet 8" below gravel road surface
 N15W 33.83', Nail & Tag in 13" Oak
 N45E 49.87', Nail & Tag in 34" Oak
 S30E 37.83', Nail & Tag in 25" Oak
 S15E 34.95', Nail & Tag in 28" Oak



Signed by Gary C. Bilow Date 8/31/93
 Surveyor's Michigan License No. 26453