

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry
 (County)

Located in: _____ Corner Code 14

- | | | | | | |
|------------------------------------|---|----|---|-----|----|
| 1. Public Land Survey | T | 3W | R | 10W | 14 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on April 01, 1993, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

14: Post established by U. S. Deputy Surveyor S. Sibley in 1831 - accessories: W. Oak 9 S30E 19 links & B. Oak 10 S56W 16.5 links. County Surveyor J. Gressy recorded in 1874 "Found GLO post and accessories." Records obtained from Wightman-Moored, Inc. dated 1984 and 1985 shows distances from corners 1-3 and H-4, but no accessories for the corners were listed.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

14: Found capped iron (D. Tobin #25876) at fence intersection. Distances to adjacent corners are consistent with Gressy measurements (North 2674.98 in 1874 vs 2674.26, South 2671.68 in 1874 vs 2671.61). Accepted capped iron as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

14: Left capped iron in place
 S40E 5.33', Nail & Tag in 14" Oak
 S53W 15.31', Nail & Tag in 16" Oak
 S11E 16.80', PK nail in 8" Oak
 West 10.04', Nail in 15" Oak



Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 8/31/93