

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Barry  
(County)

Located In: \_\_\_\_\_ Corner Code 13

1. Public Land Survey	T <u>3N</u> R <u>10W</u>	<u>13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3									●				
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary C. Bilow, in a field survey on April 01, 1993, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

13: Post established by U. S. Deputy Surveyor S. Sibley in 1831 - accessories: W. Oak 7 N64W 10 links & W. Oak 10 S63E 24 links. County Surveyor J. Gressy recorded in 1874 "Found post and set new accessories: W. Oak 12 N49W 53 links & W. Oak 10 S88E 87 links." Records obtained from Wightman-Moored, Inc. dated 1984 and 1985 stated "Fnd 3/4" iron - accessories: N & T W. side 20" Maple South 29.71. N & T NE side 26" Maple SE 42.67. N & T in 10" twin Oak ENE 67.93. Centerline Rd. North O.O. Centerline Rd. West O.O. Centerline MBT Box SW 59.7."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

13: Found 3/4" pipe and three (3) of Wightman-Moored's accessories. Accepted 3/4" pipe as the best evidence of the original GLO post.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

13: Left 3/4" pipe in place  
 S45E 42.35', Nail & Tag in 29" Maple  
 N74E 67.79', Nail & Tag in twin 11" Oak  
 S70W 59.6', Center telephone box  
 S1E 29.78', Flasher & Nail in 25" Maple  
 Centerline intersection of Upton and Kiser roads



Signed by Gary C. Bilow  
 Surveyor's Michigan License No. 26453

Date 8/31/93