

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

APR 04 2000

For corners in

Barry  
(County)

Located In: Corner Code #  
3N 10W A-3 (SW, 6)  
Yankee Springs Twp.  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

SECTION

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

2837  
Page: 1 of  
12/07/1999 08:  
Darla K. Burghdoff - Barry Co. LCROR

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on October 13, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-3 GLO - 1830-1831 Sylvester Sibley D.S. West 76.17 West boundary, 203 South of Post A.Y. Oak 28, S48°E 49'; A.W. Oak 14 N35°E 108  
1. Jan 25, 1866 A.D. Rork Bearings found  
2. May 16, 1983 L.C.R.C. #520 by James Reda, found 1" solid iron N133.98' SE corner Sec.1, T3N,R11W, tree row West, Nail in W. side dbl. 12" Oak N25°E 90.10', Nail in NE side 14" Oak N25°W 81.95', NW corner conc. Hsc, fndn. S55°E 144.38'. Iron. (SE cor. Sec. 1, T3N, R11W) North 133.98', No tree or fence line East, C/L dirt road East is North 20'±, On center line blacktop road N-S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-3 Found 1 1/2" iron pipe over 1" solid rod in mon. box, 0.03' West of Range line  
Mon. is on centerline of Patterson Road  
Nail in W. side dbl. 12" Oak N25°E 90.10'  
Replaced 1 1/2" iron in Mon. box with Barry Co. Mon. (3/4" x 36' Iron rod with cap)  
(M-3, Wayland Twp., Allegan Co.) corner is 133.94' North  
Capped rerod East 33.00'

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
12 Oct 98  
BRIAN REYNOLDS  
BR  
COUNTY SUR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-3 Replaced 1/2" iron with Barry Co. Mon. (3/4" x 36" Iron Rod with cap)  
Set nail & BC Remon tag in S. side P.Pole N70°E 99.49'  
Set nail & BC Remon tag in SE side South 15" stem of Dbl. 12"-15" Oak N30°E 89.96'  
Set nail & BC Remon tag in C/L top wood fence post N65°W 38.59'  
Set nail & BC Remon tag in E. side P.Pole N30°W 57.95'  
Allegan Co. Iron Rod with Remon cap in Mon. box (M-3, Wayland Twp., Allegan Co.) corner is 133.94' North

Signed by [Signature]  
Surveyor's Michigan License No. 39085

Date 11-22-1999

