

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

APR 04 2000

For corners in

Barry
(County)

Located In: Corner Code #
3N 10W A-4 (W 1/4, 7)
Yankee Springs Twp.
T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___

SECTION

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.



2838
Page: 1 of 1
12/07/1999 08:31

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Koerber, in a field survey on October 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-4 Corner not set by GLO
- Jan 25, 1866 A.D. Rork Found Bearings took new ones, W. Oak 20, N9°E 1.83, Hick 6 S54 1/2°E 56
 - August 3, 1976 Yankee Springs Highlands Plat, Liber 5 of Plats, Page 50, Donald Ratekin; 117.83' North to M-4 Wayland Twp. Allegan Co.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-4 Found 1/2" capped iron 0.02' west of Range line
Replaced 1/2" iron with Barry Co. Mon. (3/4" x 36" Iron rod with cap)
(M-4, Wayland Twp., Allegan Co.) corner is 117.82' North

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
12 Oct 98
BRIAN REYNOLDS
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-4 Replaced 1/2" iron with Barry Co. Mon. (3/4" x 36" Iron Rod with cap) on range line
- Set nail & BC Remon tag in N side 15" Cedar S60°W 63.32'
 - Set nail & BC Remon tag in E side 9" Maple N30°W 55.16'
 - Set nail & BC Remon tag in N. side 8" Cedar S45°E 90.50'
 - Set nail & BC Remon tag in N. side 10" Cedar N80°E 63.94'
- Allegan Co. Iron Rod with Remon cap in Mon. box (M-4, Wayland Twp., Allegan Co.) corner is 117.82' North

Signed by Steven C. Koerber
Surveyor's Michigan License No. 37085

Date 11-22-1999

