

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

APR 04 2000

For corners in

Barry
(County)

Located In: Corner Code #
3N 10W A-6 (W 1/4, 18)
Yankee Springs Twp.
T R
T R
T R
T R
S T R
S T R
S T R
S T R

SECTION

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.



2840
Page: 1 of
12/07/1999 08:11

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, Steven Koerber, in a field survey on October 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6 Corner not set by GLO

- March 3 1964 Gamble's South Shore Plat, Liber 5 of Plats, Page 17, William Hume Rogers no witnesses
- November 25, 1977. L.C.R.C. #228, Douglas Bonnema, Found 1/2" iron ; Spike in sdc. 12" Hickory NE 53.88'; PK nail in sdc. T.Pole SW 42.80'; PK nail in sdc. Guy pole SE 40.54'; On Centerline road to East and 3'± West of N-S road
- Feb. 10, 1978. Act 132 survey Liber 1, Page 453, Douglas Bonnema same wirs as No. 2 above

B. Description of corner evidence found and/or method applied in restoring or reestablishing monumentation

A-6 Found 1 1/4" iron pipe in mon.

Mon. is 0.53' West of Range line
Spike in sdc. 16" Hickory NW 60.18'
Spike in sdc. 14" Hickory SE 47.35'
Set Barry Co. Mon. (3/4" x 36' Iron rod with cap) 0.53' East of the 1' iron in mon. box
(M-5, Wayland Twp., Allegan Co.) corner is 100.24' North (GLO= 100.32')

APPROVED BY PEER REVIEW AT A MEETING HELD ON
12 Oct 98
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Set Barry Co. Mon. (3/4" x 36" Iron Rod with cap) on Range line 0.53' East of the previous 1' iron in mon. box
Set nail & BC Remon tag in S. side 16" Walnut N75E 53.68'
Set nail & BC Remon tag in N. side 14" Hickory S60°E 48.48'
Set nail & BC Remon tag in top C/C wood fence post N90W 34.91'
Set nail & BC Remon tag in NE side wood corner fence post N15W 87.81'
1" iron in mon. box West 0.53'
Allegan Co. Iron Rod with Remon cap in Mon. box (M-6, Wayland Twp., Allegan Co.) corner is 114.95' North

Signed by [Signature]
Surveyor's Michigan License No. 39085

Date 11-22-1997

