

Barry County Remonumentation

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

APR 04 2000

For corners in

Barry  
(County)

Located In: Corner Code #  
3N 10W A-7 (NW, 19)  
Yankee Springs Twp.

SECTION

1. Public Land Survey

T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

2841  
Page: 1 of  
12/07/1999 08:11

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on October 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-7 GLO - 1830-1831 Sylvester Sibley DS, West 75.26 to West Boundary 197 lks South of post; A.W.Oak 10, S54°E 48, Do. 30 N50°E 75  
 1. Nov. 12, 1866 A.D. Rork Bearings found  
 2. January 30, 1990. L.C.R.C. #405, Robert Jonker, Set corner on Twp. Line 1.97 chains (130.02') South of NE corner Section 24, T3N, R11W 1/2" iron; Spike in N. sde. 24" Hickory S88°E 33.01', Spike in NE sde. 12" twin Oak S40°E 58.52'; Spike in E. side tri-12" Oak S30°E 75.76'; 1" Solid iron North 130.02'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-7 Found nothing at corner, reset position by witnesses from L.C.R.C. #405  
 Position is 0.35' East of Range line as defined by M-7 and M-8 Wayland Twp., Allegan Co.  
 Set Barry Co. Mon. (3/4" x 36" Iron rod with cap) in mon. box on the range line 0.35' West of position called for in L.C.R.C. #405 and 130.02' South of NE corner Section 24, T3N, R11W (M-7 Wayland Twp., Allegan Co.)  
 (M-7, Wayland Twp., Allegan Co.) corner is 130.02' North (GLO= 130.02')

ACT 345 BARRY COUNTY REMONUMENTATION  
 APPROVED BY PEER REVIEW AT A MEETING HELD ON  
12 Oct 98 BR  
 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-7 Set Barry Co. Mon. (3/4" x 36" Iron Rod with cap) on Range line 0.35' West of the previous position as stated in L.C.R.C. #405  
 Set nail & BC Remon tag in N. side 24" Hickory S85°E 36.36'  
 Set nail & BC Remon tag in S. side twin 12" Hickory S45°W 58.05'  
 Set nail & BC Remon tag in W side tri-12' Oak S35°W 75.27'  
 Set nail & BC Remon tag in N. stem twin 12" Hickory S10°E 119.02'  
 Previous position per L.C.R.C. #405 East 0.35'  
 Allegan Co. Iron Rod with Remon cap in Mon. box (M-7, Wayland Twp., Allegan Co.) corner is 130.02' North

Signed by [Signature]  
 Surveyor's Michigan License No. 39085

Date 11-22-1999

