

Barry County Remonumentation

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 04 2000

For corners in

Barry
(County)

Located In: Corner Code #
3N 10W A-9 (NW, 30)

SECTION

1. Public Land Survey T___ R___ Yankee Springs Twp.

T___ R___

T___ R___

T___ R___

2. Property Controlling S___ T___ R___

in Section S___ T___ R___

3. Miscellaneous S___ T___ R___

Property in Sec. S___ T___ R___



2807

Page: 1 of 1
12/07/1999 08:3

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Steven Koerber, in a field survey on October 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		
3												
4		7		8		9		10		11		
5												
6		18		17		16		15		14		
7												
8		19		20		21		22		23		
9												
10		30		29		28		27		26		
11												
12		31		32		33		34		35		
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-9 GLO- 1830-1831 Sylvester Sibley D.S. West 75.96 to West boundary 145 lks South of Post An Elm 7 N7°E 3.93, An Aspin 9 East 7.25
 - Nov. 12, 1866 A.D. Rork Bearings found made new one B.Oak 14 S3°E 4.84 Stone and Earthen East 50
 - August 27, 1957 Valley Park Shores plat, Liber 4 of Plats, Page 24, Paul Van Kooten, P.O.B. plat 360.7' North from SW corner Sec. 19-3-10
 - September 1958 Valley Park Shores No.1 plat, Liber 4 of Plats, Page 38, Paul Van Kooten, P.O.B. plat South 1150.15 from NW corner sec. 30
 - May 5, 1965 Sunrise Shores plat, Liber 5 of Plats, Page 42, Jacob Hiestand, no witnesses (See back of page for additional information)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9 Found 3/4" pipe in mon. box 0.04' East of Range line
Spike in SE side P.Pole N65°E 37.27'
C/L Gas breather pipe N55°W 40.50'
(M-9, Wayland Twp., Allegan Co.) corner is 95.70' North

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 Oct 98

BR

BRIAN REYNOLDS

COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9 Set Barry Co. Mon. (3/4" x 36" Iron Rod with cap) in mon. box on Range line
Set nail & BC Remon tag in S. side P.Pole N70°E 37.47'
Set nail & BC Remon tag in W. side P.Pole N25°E 106.17'
Set nail & BC Remon tag in S. side 10" Spruce S80°W 59.78'
Set nail & BC Remon tag in W. side P.Pole S10°E 132.03'
Allegan Co. Iron Rod with Remon cap in Mon. box (M-9, Wayland Twp., Allegan Co.) corner is 95.70' North

Signed by [Signature]
Surveyor's Michigan License No. 39085

Date 11-22-1999

