

DEC 27 2000

SECTION

Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

Nov 20 9 08 AM '95

Sandy Schindelmarer  
REGISTER OF DEEDS

002326

Register of Deeds Stamp & File Number

Seg. #1

For corners in Barry (County) Located In: Corner Code #

1. Public Land Survey	T <u>3N</u> R <u>10W</u>	A-12 (W $\frac{1}{2}$ , 30) Yankee Springs
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on July, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12 GLO, Jan., 1826	Old notes	Survey (unrecorded)
John Mullett, D.S.	Ash stake	June, 1985
Br. Oak 7 for cor.	Swamp Oak 15" N 10	T iron
	Swamp Oak 13" N 67	SE cor. metal bldg. S 40 W 44.00'
		NE cor. metal bldg. S 70 W 27.26'
		NW cor. garg. (conc. fnd.)
		hse. #3525 S 35 E 182.68'
		Same as other wit.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12	Found T iron
	As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner and has been used as a common corner.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

August 14, 1995 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Replaced T iron w/Allegan Co. (3/4" x 24" Pin w/Cap)  
 NE cor. metal bldg. S 70 W 27.76'  
 SE cor. metal bldg. S 40 W 43.98'  
 SW cor. metal bldg. N 55 E 87.35'  
 NW cor. base for CP box S 60 E 105.34'  
 At fence cor. S & W (10'± long)  
 C/L bit. N-S, East 15'±



Signed by John C. Bueche Date Oct 2, 1995  
Surveyor's Michigan License No. 13027