

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 2 04 PM '93

Sandy Schondelmar
REGISTER OF DEEDS

Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry
(County)

Located In:

Corner Code ##

1. Public Land Survey

T 3N R 10W C-13 (SE, 31)
T _____ R _____ Yankee Springs Twp.

2. Property Controlling
in Section

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

002101

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on March, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13 DNR brass cap pad Mon. (Reynolds)
NE cor. Sec. 6 (2-10) East 12.51'
16" Oak N 60° W 4.00'
20" Oak S 20° E 20.89'
Utility pole S 80° E 3.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found DNR Mon.
Nail & #31602 cap in S side 22" Oak N 60° W 3.98'
Nail & #31602 cap in W side 24" Oak S 10° E 20.89'
Nail & #31602 utility pole N side S 80° E 3.76'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 DNR Mon.
Nail & #31602 cap in S side 22" Oak N 60° W 3.98'
Nail & #31602 cap in W side 24" Oak S 10° E 20.89'
Nail & #31602 utility pole N side S 80° E 3.76'
NW cor. wood hse. #11996 England Dr. S 30° E 87.42'
Conc. nail & B.C. Remon. tag N side 16" Oak S 65° W 27.55'
SW cor. alum. bldg. N 35° W 37.35'
NE cor. Sec. 6 (2-10) Barry Co. Mon. East 12.51'
Meas. by hand

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Signed by John C Bueche
Surveyor's Michigan License No. 13027

Date Oct 29, 1993

