

**SURVEY &  
REMONUMENTATION**

1993

**COMMISSION**

Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

MAY 14 11 08 AM '93

Sandy Schendelmarer  
REGISTER OF DEEDS

For corners in

Barry  
(County)

Located In:

Corner Code #

- |                                    |   |    |   |     |               |                     |
|------------------------------------|---|----|---|-----|---------------|---------------------|
| 1. Public Land Survey              | T | 3N | R | 10W | E-13 (SW, 33) | Yankee Springs Twp. |
|                                    | T |    | R |     |               |                     |
|                                    | T |    | R |     |               |                     |
|                                    | T |    | R |     |               |                     |
| 2. Property Controlling in Section | S |    | T | R   |               |                     |
|                                    | S |    | T | R   |               |                     |
| 3. Miscellaneous Property in Sec.  | S |    | T | R   |               |                     |
|                                    | S |    | T | R   |               |                     |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

**002016**

Register of Deeds Stamp & File Number

I, John C. Bueche in a field survey on January, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-13 LCRC #191, Jan., 1976  
1/2" iron rod in conc. with plastic cap #12029  
S 03° E 17.59' 19" W. Oak  
S 86° W 25.47' 46" B. Oak  
S 36° E 19.68' 14" W. Ash  
East 48.35' NW cor. 4, 2-10

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Found 1/2" iron with cap #12029  
@ fence cor. North & East  
As per above witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 1/2" iron with cap #12029  
Blaze & 40d nail in S side 44" Oak S 80° W 25.84'  
Blaze & 40d nail in W side 22" Oak S 05° E 17.68'  
Blaze & 40d nail in S side 22" Oak S 80° E 28.10'  
Blaze & 40d nail in E side 16" Oak S 20° E 63.88'  
Blaze & 40d nail in W side 6" Ash N 15° W 26.67'  
3/4" iron & cap #12029 NW 4, 2-10 East 48.35'  
@ fence cor. North & East  
C/L dr. North 12'±  
Meas. by hand

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by John C. Bueche Date 1-27-93  
Surveyor's Michigan License No. 13027

