

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF BARRY
 RECEIVED FOR RECORD

DEC 8 8 36 AM '94

Sandy Schindelmarer
 REGISTER OF DEEDS

002257

Register of Deeds Stamp & File Number

For corners in Barry (County)	Located in:	Corner Code #/
Public Land Survey	T <u>3N</u> R <u>10W</u>	<u>I-13 (SE, 34)</u>
	T _____ R _____	<u>Yankee Springs Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Lot No. _____, Recorded Plat _____
 Private Claims _____

John C. Bueche, in a field survey on September, 1994,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

I-13 GLO	Barry Co. Rd. Comm., does not state
W. Oak 14" N 65° E 50 lks.	what was there, 1950
W. Oak 8" N 81° W 68 lks.	26" R. Oak N 71° W 41.5'
	48" B. Oak N 21° E 26.3'
Bowen, 1875	
Stone	LCRC #191, Jan., 1976
B. Oak 10" N 53° E 52 lks. (34.32')	1 1/2" solid iron rod
W. Oak 6" N 70° E 100 lks. (66')	S 36° E 24.20' 8" Oak
	S 21° W 19.38' 5" Oak
	N 87° W 42.75' 32" Oak

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found large stone 10" dia. x 20" deep, referenced by Bowen, 1875
 which checks ALLEN'S ACRES SUB., recorded in Feb., 1962
 Found 1 1/2" pipe 12'± South & 11'± West, LCRC #191
 Found 1 1/2" pipe 11'± South & 4'± West
 And is accepted as a careful and faithful perpetuation of the position
 of the original corner.

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
BR DEC 8, 1994
 BRIAN REYNOLDS COUNTY SURVEYOR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Replaced stone with Barry Co. Mon. (3/4" x 24" Pin with Cap)
 on top 3/4" x 24" Pin
 Nail & Barry Co. Remon. Tag in N side 24" Oak N 90° E 59.44'
 Nail & Barry Co. Remon. Tag in NW side 14" Oak N 60° E 33.78'
 Nail & Barry Co. Remon. Tag in E side 10" Oak S 25° E 55.67'
 Nail & Barry Co. Remon. Tag in W side 12" Oak S 25° W 48.33'
 Nail & Barry Co. Remon. Tag in E side 6" Oak S 55° W 66.50'
 N edge of 2 track E-W, South 12'±
 C/L bit. (Yankee Springs Rd.) West 520'±
 1 1/2" pipe 12'± South & 11'± West
 1 1/2" pipe 11'± South & 4'± West

Signed by John C. Bueche
 Surveyor's Michigan License No. 13027

Date 10-26-94

