

OCT 25 1993

COMMISSION

BARRY COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF BARRY
 RECEIVED FOR RECORD

SEP 7 3 33 PM '93

Sandy Schondelmayer
 REGISTER OF DEEDS

002086

Register of Deeds Stamp & File Number

For corners in
Barry
 (County)

Located In: Corner Code #

YANKEE SPRINGS TWP.

1. Public Land Survey	T	<u>3N</u>	R	<u>10W</u>	<u>K5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on April 01, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K5: Post established by U.S. Deputy Surveyor S. Sibley in 1831 - accessories: W. Oak 12 S1/2E 299 links & Y. Oak 22 East 264 links. Undated County Road Commission Records do not list what was found or set - accessories: N10W 153.4' 14" B. Oak. S45W 61.9' 4" R Oak, S40E 50.5' 8" B. Elder. Records dated 1986 obtained from Tri-County Land Surveys state "Found 3/4" Spike - accessories: Nail in SE side 19" Oak SW 61.35", PK top 8" T.P. ESE 50.07', Centerline Flag pole NE 103.10', Centerline top Tel. Cab. Bx WNW 60.92'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K5: Found 3/4" spike in center of intersection of Yankee Springs and Howens Mill roads and none of the previous witnesses. Accepted this iron as the best evidence of the GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K5: Replaced 3/4" spike with 1/2" rebar with plastic cap stamped "G.C. Bilow LLS #26453" in Monument box
 S38W 62.00', Nail & Tag in 21" Oak
 S64E 50.15', PK nail top of 3" post
 N80E 120.00', Nail & Tag in 21" Oak
 N67W 60.95', Center telephone box
 Center of intersection of Yankee Springs and Howens Mill Roads



Signed by Gary C. Bilow Date 8/31/93

Surveyor's Michigan License No. 26453

10/26/93