

**SURVEY & REMONUMENTATION**

**BARRY COUNTY REMONUMENTATION**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECORDS DEPARTMENT

JUL 24 1997

MAR 5 9 25 AM '97

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **BARRY**  
(County)

Located In: Corner Code #

1. Public Land Survey				
<b>CENTER OF SECTION</b>	T	<b>3N</b>	R	<b>10W</b>
<b>12 YANKEE SPRINGS</b>	T		R	
<b>TOWNSHIP</b>	T		R	
	T		R	
2. Property Controlling in Section	S		T	R
	S		T	R
3. Miscellaneous Property in Sec.	S		T	R
	S		T	R

**L-4**

Sandy J. Reynolds  
REGISTER OF DEEDS

**002482**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**BRIAN REYNOLDS**

**17 AUGUST**

**96**

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11								
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

**1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.**

**\*\*\* NO HISTORICAL INFORMATION, PUBLIC OR PRIVATE, COULD BE FOUND FOR THIS CORNER \*\*\***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**TRAVERSED ENTIRE SECTION 12 TYING IN OCCUPATION AND OTHER CORNERS. WHILE NO RECORD COULD BE FOUND FOR BREAKDOWN OF SECTION 12, OCCUPATION LINES INDICATE A SURVEY WAS DONE MANY YEARS AGO, BUT NOT PLACED ON RECORD. AT INTERSECTION OF TRACES OF FENCES WEST AND SOUTH, FOUND A SINGLE BRICK STANDING UPRIGHT WITH PIECES OF BRICK AROUND IT. THE COUNTY SURVEYOR NOTES FOR THE SOUTH 1/4 CORNER OF SECTION 12 BY LEE S. COBB, 1895, STATE "FOUND OLD STAKE & BRICK SET NEW STAKE" L.2, P.204. AT THE SOUTH 1/4 CORNER, WE RECOVERED BRICKS REMARKABLY SIMILAR TO THE BRICKS FOUND AT L-4. FROM THIS, I CONCLUDE THAT THE BRICKS AT CENTER OF SECTION AND SOUTH 1/4 CORNER OF SECTION 12 WERE PLACED BY THE SAME SURVEYOR, NAME AND DATE UNKNOWN, PRIOR TO 1895. ACCEPTED FOUND BRICK AS PROPER ESTABLISHMENT OF CORNER. REPLACED FOUND BRICKS WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND CAP.**

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON


9-9-96

BRIAN REYNOLDS

COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (WITH ALUMINUM CAP)
- SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF AN 8" ASH NORTH 2.92'
- SET 20d NAIL W/REMON TAG IN THE SOUTHWEST SIDE OF A 16" OAK N42°W 27.99'
- SET 20d NAIL W/REMON TAG IN THE SOUTHEAST SIDE OF A 15" OAK N58°E 24.15'
- SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 15" OAK S46°E 31.56'
- SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A 24" OAK S12°E 46.52'
- SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A 12" OAK S73°W 32.94'
- SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 12" OAK N74°W 31.86'
- TRACES OF OLD FENCE IN GROUND TO WEST AND SOUTH



Signed by *Brian Reynolds*

Date FEB 17, 1997

Surveyor's Michigan License No. 31602