

SURVEY & REMONUMENTATION
 AUG 22 1995
 COMMISSION

STATE OF MICHIGAN
 COUNTY OF BARRY
 RECEIVED FOR RECORD
BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 8 34 AM '95

For corners in
BARRY
 (County)

Sandy Schondelmar
 REGISTER OF DEEDS

1. Public Land Survey	T	<u>3N</u>	R	<u>10W</u>	Corner Code #	<u>M-4</u>
E 1/4 CORNER SECTION 12	T		R			
YANKEE SPRINGS TOWNSHIP			R			
ON RANGE LINE	T		R			
2. Property Controlling in Section	S		T	R		
3. Miscellaneous Property in Sec.	S		T	R		
4. Lot No. _____, Recorded Plat _____						
5. Private Claims _____						

002264

Register of Deeds Stamp & File Number

BRIAN REYNOLDS in a field survey on **22 OCTOBER** 19**1994**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: L. LYON, D.S., 1826 (R10W, P.108), W. OAK 12 S2°W 666 Do. 10 N8°W 308**
- NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A-5, T3N, R9W, AND M-3, T3N, R10W. RESTORED M-5, T3N, R10W, AND A-3, T3N, R9W. COMPUTED POSITION FOR A-4 AT MID-DISTANCE AND ON RANGE LINE, EXCAVATED AT THAT LOCATION, 1.5' WEST OF EAST EDGE OF GRAVEL ROAD THROUGH 1' OF STABILIZED GRAVEL, 6" OF ROAD SAND, 6" OF BLACK SAND INTO BLACK PEAT, A 6' BY 5' EXCAVATION CENTERED ON COMPUTED POINT, FOUND NOTHING. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT MID-POINT BETWEEN A-3 AND A-5 ON RANGE LINE.

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
1 NOV. 1994 BR
 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
 SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A UTILITY POLE S19°W 123.53'
 SET 40d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 36" OAK S60°E 34.58'
 SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 22" OAK S28°E 51.80'
 SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 12" OAK N68°E 27.94'
 7' EAST OF APPROXIMATE CENTERLINE OF PEETS ROAD
 46.64' SOUTH OF THE WEST 1/4 CORNER OF SECTION 7, T3N, R9W**



Signed by Brian Reynolds
 Surveyor's Michigan License No. 31602

Date JANUARY 24, 1995