

SURVEY & REMONUMENTATION

SEP 14 1999

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JAN 25 8 34 AM '95

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schindelmarer
REGISTER OF DEEDS

For corners in
BARRY

(County)

Located In: Corner Code #

T 3N R 10W M-5
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

002263

Register of Deeds Stamp & File Number

1. Public Land Survey
CORNER COMMON TO
SECTIONS 12 & 13
YANKEE SPRINGS TOWNSHIP
ON RANGE LINE

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

BRIAN REYNOLDS

22 OCTOBER

1994

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: L. LYON, D.S., 1826 (R10W,P.107) B. OAK 9 S5W 80 W. OAK 18 N4W 312**
 - COUNTY SURVEYOR RECORDS: LEE COBB, 1895 (L.2,P.284) "FOUND & SET IRON SHAFT 2 X 18 WITH PINION ON END 2 X 18in"**
 - NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
PRELIMINARY CHECK OF LOCATION FOR M-5 REVEALED NO MAGNETIC MONUMENTATION. FOUND M-3, T3N, R10W, A-5 AND A-2 T3N, R9W. TRAVERSED ALL OF SECTION 7, T3N, R9W, RESTORED A-3, T3N, R9W, AND COMPUTED POSITION FOR M-5, AT GOVERNMENT JOG, EXCAVATED AND FOUND BITS OF BRICK IN A SMALL AREA AT THE GOVERNMENT JOG. POSITION FITS VERY WELL WITH EXTENDED CENTERLINE OF ROAD TO THE WEST, AND WITH RANGE LINE. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT GOVERNMENT JOG, ON RANGE LINE (MONUMENT POSITION IS INSIDE THE AREA OF FOUND BRICK)

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

1 NOV. 1994 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
**SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 30" OAK S5°E 99.30'
SET 40d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 14" OAK S37°W 63.37'
SET 40d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 16" TRIPLE CHERRY S63°W 61.02'
SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A TRIPLE OAK N66°W 79.20'
APPROXIMATELY ON CENTERLINE OF PEETS ROAD EXTENDED SOUTH
APPROXIMATELY ON CENTERLINE OF BOWEN'S MILL ROAD EXTENDED EAST
38.94' SOUTH OF THE SOUTHWEST CORNER OF SECTION 7, T3N, R9W**



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date JANUARY 24, 1995