

**SURVEY & REMONUMENTATION**

**BARRY COUNTY REMONUMENTATION**

JUL 24 1997

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

**002495**

For Corners in BARRY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(county)

STATE OF MICHIGAN  
BARRY COUNTY  
RECORDED  
17 JUN 97 12:18 P.M.  
SANDY SCHONDELHAYER  
REGISTER OF DEEDS

1. Public Land Survey T 4N R 8W M-1 Barry  
TOWNSHIP CORNER T 4N R 7W A-1 Barry  
COMMON TO T 5N R 7W A-13 Ionia  
TOWNSHIPS 4 & 5 NORTH T 5N R 8W M-13 Ionia  
RANGES 7 & 8 WEST
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

T 5N R 8W  
M-13

	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **Brian Reynolds**, in a field survey on 17 OCTOBER, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1826 (R8W, P.138) BEECH 11 N70E 19 SUGAR 8 N68W 13 1/2
  - NO REFERENCE FOUND IN THE BARRY COUNTY SURVEYOR RECORDS.
  - BARRY COUNTY ROAD COMMISSION: NO NAME OR DATE "IRON AND STONE" U.P. N45W 42.3' U.P. GUY S45W 36.3' 30" ELM S50E 46.3'
  - IONIA COUNTY ROAD COMMISSION, 1958 3/4" IRON PIN P. POLE N45°W 42.74' GUY POLE N44°E 36.50' 30" ELM S56°E 47.40' ROAD SIGN S44°W 36.45'

\*\*\* NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER \*\*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND A 6" BOAT SPIKE FLUSH WITH PAVEMENT. EXCAVATED AND FOUND A 12" BOAT SPIKE DIRECTLY UNDER 6" BOAT SPIKE. NO WITNESSES RECITED IN PART "A" COULD BE FOUND. ACCEPTED FOUND BOAT SPIKES AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.

REPLACED FOUND BOAT SPIKES WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.  
FOUND NAIL W/CAP #28424 IN THE NORTHWEST SIDE OF A UTILITY POLE S47°W 41.69'  
FOUND NAIL W/CAP #28424 IN THE SOUTH SIDE OF A 22" MAPLE N79°W 165.07'  
FOUND NAIL W/CAP #28424 IN THE SOUTH SIDE OF A 12" WALNUT N79°E 126.66'  
FOUND NAIL W/CAP #28424 IN THE NORTH SIDE OF A UTILITY POLE S84°E 209.02'  
SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A GUY POLE N85°E 209.87'  
CORNER IS ON CENTERLINE OF NORTH-SOUTH-EAST-WEST ROADS

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
5-3-94  
**BRIAN REYNOLDS** COUNTY SURVEYOR



Signed by [Signature]  
Surveyor's Michigan License No 31602

Date May 16, 1997  
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971