

SURVEY & REMONUMENTATION

BARRY COUNTY REMONUMENTATION

FEB 03 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in
BARRY
(county)

Located in:

Corner Code #



2695

Page: 1 of 1
11/25/1998 12:13P

Sandy Schondelmayer - Barry Co. LCRCR

1. Public Land Survey
WEST 1/4 CORNER
SECTION 30
WOODLAND TOWNSHIP
ON RANGE LINE

T 4N R 7W
T _____ R _____
T _____ R _____
T _____ R _____

A-10

2. Property Controlling
in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 9 OCT., 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE
 - NO MENTION OF THIS CORNER COULD BE FOUND IN THE COUNTY SURVEYOR RECORDS.
 - LAND CORNER RECORDATION CERTIFICATE: #189 (FOR M-10, CARLTON TWP.), BY GEORGE YOUNG, P.S. #17640, 25 NOV. 1975 SET 1/2" RE-ROD WITH CAP ACCORDING TO GOVERNMENT REGULATIONS." NAIL IN 6" MAPLE N10°W 43.93'
TOP ANGLE IRON FENCE POST S05°W 17.55' NAIL IN 6" ELM S45°E 72.98'

*** NO HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND SLIGHT MAGNETIC EVIDENCE 8'+/- NORTH OF FENCE CORNER OCCUPATION WEST AT APPARENT CORNER LOCATION FOR M-10, CARLTON TWP. EXCAVATION WITH BACKHOE REVEALED A VERTICAL RING OF SMALL-MEDIUM SIZED STONES, SIMILAR TO WHAT WE FIND AROUND A FENCE CORNER POST. VERTICAL RING OF STONES EXTENDED TO A DEPTH OF 3.5'+. ALSO FOUND VERY OLD FENCE WIRE 2-3 FEET BELOW GRADE SHAPED AS THOUGH IT WAS WRAPPED AROUND A FENCE POST AND RUNNING TO THE WEST. CENTER OF VERTICAL RING OF STONES LIES 4.18' EAST OF LINE FROM FOUND STONE AT M-11 TO REMONUMENTED M-9 & 0.70' SOUTH OF THE MIDPOINT. EXCAVATION AT MID POINT BETWEEN REMONUMENTED A-11 AND REMONUMENTED A-9 REVEALED NO EVIDENCE OF PREVIOUS MONUMENTATION.
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT MID POINT BETWEEN A-9 AND A-11 AND ON LINE BETWEEN REMONUMENTED M-9 AND REMONUMENTED M-10.
DISREGARDED POSITION FOR M-10 AS RECORDED BY GEORGE YOUNG (ITEM #3 ABOVE).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
TOP CENTER OF AN ANGLE IRON FENCE CORNER POST IN CONCRETE S60°W 35.45'
SET 60d NAIL IN THE SOUTHEAST SIDE OF A 22" ELM S48°E 49.78'
TOP CENTER OF A TELEPHONE RISER N88°E 25.22'
FOUND 1/2" IRON (GEORGE YOUNG) N75°W 25.59'
CORNER LIES 1'+/- WEST OF NORTH-SOUTH GRAVEL CENTERLINE
17'+/- NORTH OF FIELD SEAM RUNNING WEST
M-10, T4N, R8W, CARLTON TOWNSHIP, LIES SOUTH 9.22'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
12 OCT. '98
BRIAN REYNOLDS
COUNTY SURVEYOR



Signed by Brian Reynolds
Surveyor's Michigan License No. 31602

Date Nov 24, 1998
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 1971