

**SURVEY &
REMONUMENTATION**

APR 08 1996

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

Nov 8 10 48 AM '95

Sandy Schondelmaier
REGISTER OF DEEDS

002311

For corners in
BARRY

(County)

Located In:

Corner Code #

- | | | |
|---|-------------------------|------------|
| 1. Public Land Survey
1/4 COR. COMMON TO
SECS. 5 & 6
WOODLAND TWP. | T <u>4N</u> R <u>7W</u> | <u>C-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RAYMOND MOORED

10 MAY

94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration.
SEE BACK OF THIS FORM FOR PART A

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON REROD PER LCRC 420 BY REYNOLDS. ALL WITNESSES REMAINED.
ACCEPTED POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.
REMOVED 1/2" REROD AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
OCTOBER 9, 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
-NAIL IN SE SIDE OF 36" WALNUT N88°W 37.00"
-NAIL IN NW SIDE NOWER POLE N35°E 49.36'
-NAIL IN SW SIDE 28" WALNUT N30°W 63.58'
-EAST EDGE OF 2" X 2" ANGLE IRON FENCE CORNER DUE WEST 27.25'



Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 11/1/95

PART-A:

GOVERNMENT LAND OFFICE: S. SIBLEY, D. S., 1830 (R7W, P. 158) SUGAR 7 S50E 21, BEECH 8 N72W 32.

CO. SURVEYOR:

COBB, 29 MAY, 1913 FOUND OLD STAKE AND 3 STONES; SET GAS PIPE, STONE AND BRICK.
B. WALNUT 12 WEST 20' (DARK BROWN WOODLAND FIELD BOOK, PAGE 59)

COUNTY ROAD COMMISSION:

(ROAD # 42-50 FIELD BOOK, PG.6, NO DATE) STATION 341 + 19.1 SET BRIDGE SPIKE.
N0°-31' E, DEFL ANGLE= 0°-05' RT ROAD EAST

24" WALNUT N88W 37.3'

FENCE POST WEST 27.2'

8" WALNUT N30W 63.6'

IRON FENCE POST S70E 66'

LCRC # 420 RECORDED 9 OCTOBER, 1990 BY BRIAN REYNOLDS, P.S. NO 31602. FOUND NO
MONUMENT. SET 1/2" IRON REROD FROM REMAINING ROAD COMMISSION WITNESSES.

-40d SPK IN . SIDE 30" WALNUT N88W 38.51'

-SPK IN POWER POLE N40E 49.52'

-FACE OF ANGLE IRON FENCE POST WEST 27.2'

-0.5' EAST OF N-S CENTERLINE ON CENTERLINE EAST