

PART-A:

GOVERNMENT LAND OFFICE: S. SIBLEY, D. S., 1830 (R7W, P. 158) BEECH 12 S74W 18, BEECH 20 N88E 13.

CO. SURVEYOR:

A.C. WILLSON, OCT, 1892 (L. 2, PG. 278) CORNER GONE. ESTABLISHED CORNER BY CROSSING SECTION LINES & DROVE AN IRON BAR 4' LONG INT THE GROUND; ELM 14 N75W 2.67, ELM 16 N71E 2.17. (AT THE TIME MENTIONED, MR. A. C. WILLSON WAS A RESIDENT OF EATON COUNTY AND HAD BEEN FOR SOME MONTHS AND WAS NOT COUNTY SURVEYOR OF BARRY OR ANY OTHER COUNTY. LEE COBB, 1893)

COBB, 28 JUNE 1909 FOUND OLD STAKE 18 LONG IN PIT OF STONES; SET IRON PUMP JACKET; CORNER OF CHURCH N43-1/2W 1.375 CHS
CORNER OF SCHOOL HOUSE S44-1/2E 2.465 CHS.
(DARK BROWN WOODLAND FIELD BOOK, PAGE 71)

COBB 29 MAY, 1913 FOUND IRON PUMP TOP FOR CORNER (MARGINAL NOTES IN GLO NOTES, PG.57, BROWN WOODLAND FIELD BOOK).

COUNTY ROAD COMMISSION:

(ROAD # 42-50 FIELD BOOK, PG.5, NO DATE) STATION 315 + 18.9 DID NOT FIND CORNER, SET BRIDGE SPIKE.

N0°-26' E, DEFL ANGLE= 88°-18' LT.

10" ELM S15W 72.0'

IRON SIGN POST S45E 45.5'

GUY POLE N50E 64.8'

36" ELM N75W 166.0'