

**SURVEY &
REMONUMENTATION**

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

APR 26 1995 FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

COMMISSION

002259

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	Woodland Township T. <u>4</u> N. S., R. <u>7</u> E. W.	F-7
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

STATE OF MICHIGAN
 COUNTY OF BARRY
 RECEIVED FOR RECORD
 Dec 13 11 08 AM '94
 Sanday S. Reynolds
 REGISTER OF DEEDS
 REGISTER OF DEEDS STAMP AND
 FILING NUMBER

I, Earl S. Strater, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 21, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 11" Beech N52°E 37'	Hwy. Plans 10/14/55 3/8" iron	B.C.R.C. stone/iron
4" Beech S60°E 3 1/2'	power pole S04°E 25.24'	telephone pole N72°W 70.52'
	telephone pole N67°W 70.44'	18" maple S73°E 103.97'
	fence post N02°W 27.88'	power pole S10°W 25.05'
King & Carr 12/84 1" iron in casting		10" cherry N68°E 67.7'
nail w/shiner North 59.84'		
North pt. 3 corner conc. marker South 37.27'		
SE corner headwall S35°W 29.41'		

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1" solid iron 9" deep in monument box, 1' south of C/L of M-43

No accessories found.

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
6 DEC 1994 BR
 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" solid iron 9" deep in monument box 1' south of C/L of M-43
 Nail w/cap east face power pole N06°E 81.41'
 Top center of ROW marker S30°W 38.34'
 Chiseled "x" on north end concrete culvert N35°W 39.45'
 Chiseled "x" on south end concrete culvert S35°W 39.30'



SIGNED BY Earl S. Strater DATE December 9, 1994

SURVEYOR'S MICHIGAN REGISTRATION NO. 28424

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____