

**SURVEY &  
REMONUMENTATION**

**BARRY COUNTY REMONUMENTATION**

**APR 2 1995 AND CORNER RECORDATION CERTIFICATE**

**COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

**002260**

FOR CORNERS OF--:	LOCATED IN--:	Woodland Township	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>4</u> N. S., R. <u>7</u> E. W.		<u>G-7</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____	RECORDED PLAT _____		
5. PRIVATE CLAIMS _____			

STATE OF MICHIGAN  
 COUNTY OF BARRY  
 RECEIVED FOR RECORD  
**DEC 13 11 08 AM '94**  
 Sandy Schmalzberger  
 REGISTER OF DEEDS  
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Earl S. Strater, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 21, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O. 10" Sugar S59 1/2°W 34 links  
 28" Beech N59 1/2°E 17 links

J.W. Haughtalin, May 11, 1869  
 stone 31" at bottom, 15" at top, cross on stone and cinders under it.

King & Carr, December 1984  
 1" solid iron in monument box

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Found 3/4" axle with 1" round top in monument box at the intersection of M-43 and Woodland Road.

No accessories found.

ACT 345 BARRY COUNTY REMONUMENTATION  
 APPROVED BY PEER REVIEW AT A MEETING HELD ON

6 DEC 1994 BR  
 BRIAN REYNOLDS COUNTY SURVEYOR

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3/4" axle with 1" round top in monument box at the intersection of M-43 and Woodland Road.

Nail w/cap SW face power pole N58°W 51.00'  
 SE corner brick building N42°W 49.65'  
 Nail w/cap NW face power pole S46°W 43.50'  
 SW corner of building N29°E 94.77'



SIGNED BY Earl S. Strater DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 28424

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_