

**SURVEY &  
MONUMENTATION**

APR 08 1996

**COMMISSION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

Nov 8 10 48 AM '95

Sandy Schondelmayer  
REGISTER OF DEEDS

002306

Register of Deeds Stamp & File Number

For corners in  
**BARRY**

(County)

Located In:

Corner Code #

1. Public Land Survey SEC. COR. COMMON TO SEC'S. 2,3 WOODLAND TWP.	T <u>4N</u> R <u>7W</u>	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**RAYMOND MOORED**

**24 AUG.**

**94**

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

GENERAL LAND OFFICE S. SIBLEY, D.S. 1830( R7W PG 141) W. OAK 38 S72E 40; W ASH 11 S45W 20  
BOWEN OCT7-9, 1878 (L-1, PG 261) LIMESTONE FOR CORNER ( NO WITS)  
CO. ROAD COMM. (1955 HWY PLANS PG 9) 3/4" PIPE & BT. SPIKE FOR COR. 18" CEDAR S60W 52.05',  
28" WALNUT N49E 94.85', TELE POLE # 1104 N72E 88.20', POWER POLE N46W 45.50'  
36.30' WEST OF IONIA CORNER  
LCRC # 328 (JAMES PORTER, RLS # 19003, REC 1-11-82) FOUND 3/4 " PIPE AND BOATSPIKE PER ROAD  
COMM WITS. ABOVE. TOOK NEW WITS: NAIL & TAG IN P. POLE NW 43.24', NAIL & TAG IN P POLE NNW 30.45'  
NAIL & TAG IN P. POLE SSW 50.24', TWIN 26" CEDAR SW 51.80'  
IONIA COUNTY CORNER DUE EAST 36.31'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 3/4" IRON PIPE 20" DEEP AS PERPETUATED BY PORTER IN LCRC 328. FOUND 4 OF 5 WITNESSES  
REMAINING. ACCEPTED PIPE AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.  
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP OVER EXISTING PIPE

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

OCT 9, 1995 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.  
-NAIL & TAG IN TWIN 26" CEDAR S60°W 52.30'  
-NAIL & TAG IN TELE POLE N45°E 81.00'  
-NAIL & TAG IN POWER POLE N45°W 43.50'  
-NAIL & TAG IN POWER POLE N10°W 30.23'  
-IONIA COUNTY CORNER (I-13) DUE EAST 36.32'



Signed by Raymond E. Moored

Date 11/1/95

Surveyor's Michigan License No. 26463