

APR 08 1996

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

Nov 8 10 48 AM '95

Sandy Schondelmarer

REGISTER OF DEEDS

002312

For corners in
BARRY

(County)

Located In:

Corner Code =#

| | | |
|---|-------------------------|------------|
| 1. Public Land Survey SEC. COR. COMMON TO SEC'S. 2,3,10,11 WOODLAND TWP. | T <u>4N</u> R <u>7W</u> | <u>1-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RAYMOND MOORED

24 AUG.

94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE S. SIBLEY, D.S. 1830(R7W PG 140) SUGAR 7 N15E 27; BEECH 12 S45W 21.5 BOWEN OCT7-9, 1878 (L-1, PG 260) SET STONE & BRICK WITS: ASPEN 16 N11-1/2W 174, CHERRY 12 S65W 106 CO. ROAD COMM. (1955 HWY PLANS PG 11) STONE & PIPE FOR COR. 13" ELM S59E 55.40', 10" OAK S14W 130.00', 25" CHERRY S65W 72.20', 11" ELM N72W 78.33' SET MON BOX ON COR 1-29-73

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MON BOX PER CO. ROAD INFO. NO WITNESSES REMAIN. POSITION OF CORNER IS CONSISTENT WITH MDOT STATIONING EAST TO J-3. PROBED MON BOX AFTER PIPE WAS REMOVED BUT DID NOT LOCATE STONE. ACCEPTED PIPE AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
OCTOBER 9, 1995
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.
-NAIL IN NORTH SIDE 12" CHERRY S80°E 79.18'
-NAIL IN SE SIDE TELE POLE N45°E 171.05'
-NAIL IN SOUTH SIDE 30" OAK N80°W 127.65'
-NAIL IN SW SIDE 12" MAPLE N78°W 195.93'



Signed by

Raymond Moored

Date

11/1/95

Surveyor's Michigan License No.

26463