

SURVEY & REMONUMENTATION

FEB 17 1998

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in
BARRY
(county)

Located In:

Corner Code



2661

Page: 1 of 1
12/18/1997 07:49A

1. Public Land Survey
**CORNER COMMON TO
SECTIONS 10, 11, 14, & 15
WOODLAND TOWNSHIP**

T 4N R 7W 15
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **Brian Reynolds**, in a field survey on **3 APRIL, 1997** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R7W, P.139) SUGAR 15 N55 1/2W 44 SUGAR 12 S71E 36
2. CHICAGO, KALAMAZOO, & SAGINAW RAILROAD (L.1 OF PLATS, P. 34), 8 NOVEMBER, 1888, "1541' WEST OF C. K. & S. RAILROAD"

NO OTHER INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND NO EVIDENCE OF MAGNETIC MONUMENTATION. NO OCCUPATION AVAILABLE TO THE NORTH, EAST, OR SOUTH.
DISTANCE TO 1/8 LINE OCCUPATION WEST IS 1328.25' AND TO 1/4 LINE OCCUPATION IS 2658.00'.

EXCAVATION REVEALED NO EVIDENCE OF CORNER MONUMENTATION.

ACCEPTED INTERSECTION OF CENTERLINES AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/REMON TAG IN THE NORTHEAST SIDE OF A UTILITY POLE N58°W 64.18'
SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A UTILITY POLE N75°E 136.58'
SET 20d NAIL W/REMON TAG IN THE SOUTHWEST SIDE OF A UTILITY POLE S45°E 43.92'
SET 20d NAIL W/REMON TAG IN THE SOUTHWEST SIDE OF A UTILITY POLE S9°W 323.31'
SET 20d NAIL W/REMON TAG IN THE WEST ROOT OF A 36" BLACK OAK S4°E 378.55'
ON CENTERLINE OF EAST-WEST GRAVEL ROAD ON CENTERLINE OF NORTH-SOUTH BITUMINOUS ROAD

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
14 April '97
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date Dec 18, 1997
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 28, 1971
REVISED MAY 14, 1975 REVISED JANUARY, 1983 REVISED OCTOBER 1995