

APR 08 1996

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 12 2 07 PM '95

Sandy Schondelmarjer
REGISTER OF DEEDS

002331

Register of Deeds Stamp & File Number

For corners in
BARRY

(County)

Located In:

Corner Code ##

1. Public Land Survey SEC. COR. COMMON TO SEC'S. 22, 23, 26, 27 WOODLAND TWP.	T	4N	R	7W	I-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RAYMOND MOORED

17 JUNE

94

I, RAYMOND MOORED, in a field survey on 17 JUNE, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration.

GLO: S. SIBLEY, D.S. 1830 (R7W, PG. 137-138) SET STAKE; SUGAR 11 N83W 26, BEECH 10 N66E 27 BOWEN 1875, (L. 1, PG. 93) STAKE AND STONE.
CO. ROAD COMM.: STONE AND TILE, (NO DATE)
COR. POST N45W 42.0'
16" CHERRY S70E 108.8 (OUT)
20" CHERRY N70E 123.2' (OUT)
CO. ROAD COMM: 4-3-80 JLV & BM
N10W POWER POLE 111.70'
N60W TELE PEDESTAL MARKER(WOODEN POST) 59.00'
S45E ROAD SIGN POST 49.00'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
NOV 13, 1995
BRIAN REYNOLDS
COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE 1.5' DEEP FROM COR. POST AND POWER POLE WITNESSES ABOVE. REMOVED BOAT SPIKE AND PROBED FOR STONE AND TILE. FOUND NOTHING. FROM FOUND POSITION MEASURED EAST TO K-9. PRORATED MEASURED DISTANCE AGAINST BOWEN'S 1875 DISTANCE TO ESTABLISH J-9. PRORATED POSITION MISSED OCCUPATION LINE NORTH AT J-9 BY APPROX 4'. MEASURED WEST FROM FOUND I-9 1/4 AND 1/2 MILE TO H-9. OCCUPATION LINES INDICATED I-9 SHOULD BE 6.5 FEET FURTHER EAST FROM FOUND LOCATION. DUG 6.5' EAST FOR STONE AND FOUND NOTHING. PRORATING FROM EASTERLY MOST POSITION TO K-9 AGAINST BOWENS 1875 MEASUREMENT FIT J-9 OCCUPATION WITHIN 1'. ACCEPTED POSITION 6.5' EAST OF FOUND CORNER AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. THIS POSITION ALSO MATCHES PROPERTY LINE 495' (30 RODS) SOUTH AS SURVEYED BY BOWEN IN 1875. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
-FACE OF 4" STEEL CORNER FENCE POST N55°W 46.84'
-NAIL AND TAG IN SOUTH SIDE CUT OFF POWER POLE N70°W 64.78'
-NAIL AND TAG IN EAST SIDE POWER POLE 188.66'
-NAIL AND TAG IN EAST SIDE POWER POLE N35°W 117.80'



Signed by Raymond Moored

Date 11/17/95

Surveyor's Michigan License No. 26463