

APR 08 1996

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

DEC 12 2 07 PM '95

Sandy Schondelmayer REGISTER OF DEEDS

002332

Register of Deeds Stamp & File Number

For corners in BARRY

(County)

Located In:

Corner Code ##

- 1. Public Land Survey 1/4 SEC. COR. COMMON TO SEC'S. 23 & 26 WOODLAND TWP. T 4N R 7W J-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

RAYMOND MOORED

17 JUNE

94

I, RAYMOND MOORED, in a field survey on 17 JUNE, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column I and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: S. SIBLEY, D.S. 1830 (R7W, PG. 138) SET STAKE; SUGAR 24 N63W 18.5, BEECH 7 S10E 8.5 BOWEN 1875, (L.1, PG. 93) STAKE WITH CINDERS FROM FORGE, MAPLE STUMP 36 S521/2W 59

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

EXISTING ROAD IN CUT SECTION. ALL EVIDENCE OF ORIGINAL CORNER GONE. MEASURED MILE DISTANCE FROM I-9 TO K-9 AND PRORATED DISTANCE AGAINST DISTANCE BY BOWEN IN 1875. POSITION FELL WITHIN 1 FOOT OF MIDPOINT OF MILE AND FIT OCCUPATION LINE TO NORTH. SET CORNER MIDWAY AND ON LINE BETWEEN I-9 AND K-9. ACCEPTED POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON Nov 13, 1995 BR BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
-NAIL AND TAG IN SE SIDE CORNER FENCE POST N35°E 36.19'
-NAIL AND TAG IN EAST SIDE 8" WALNUT DUE NORTH 31.62'
-NAIL AND TAG IN EAST SIDE 4" HICKORY N5°W 34.75'
-NAIL AND TAG IN SW SIDE POWER POLE N60°W 106.83'



Signed by Raymond Moored

Date 11/17/95

Surveyor's Michigan License No. 26463