

**SURVEY &
REMONUMENTATION**

APR 08 1996

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

Nov 8 10 48 AM '95

Sandy Schondelmarer
REGISTER OF DEEDS

002307

Register of Deeds Stamp & File Number

For corners in
BARRY

(County)

Located In:

Corner Code #

- | | | |
|---|-----------|-----|
| 1. Public Land Survey
1/4 SEC. CORNER COMMON
TO SEC'S 23,24,
WOODLAND TWP. | T 4N R 7W | K-8 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling
in Section | S T R | |
| | S T R | |
| 3. Miscellaneous
Property in Sec. | S T R | |
| | S T R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RAYMOND MOORED, in a field survey on **24 SEPT.**, 19**94**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE S. SIBLEY, D.S., 1830(R7W, P.134) W. ASH 30 S36W 5/ BEECH 6 N15E 5 COBB, 4-15-09, SET STONE AND BRICK (NO WITS) CO. RD. COMM WITS- 18" MAPLE 83.4' E	MDOT STATION 416+84.70(PROJ NO. 8-32) 14" WALNUT S46E 27.97 TEL POLE S61W 29.82' 16" WALNUT N50W 52.46' (1953 & 57 HWY PLANS)
10' WALNUT 77.5' W	
14" WALNUT S46E 27.97'	
TEL POLE S61W 29.82'	
16" WALNUT N50W 52.46'	
STATION 398+29 (ROAD PLANS)	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON BAR IN MON. BOX PER MDOT INFORMATION
NO WITNESSES REMAINED. DISTANCE TO SW CORNER (K-9) MATCHED MDOT STATIONING.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

JULY 10, 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
NAIL & TAG IN N. SIDE POWER POLE S80°E 58.57'
NAIL & TAG IN SW SIDE POWER POLE N45°W 106.55'
NAIL & TAG IN SW SIDE 15" MAPLE S45°E 115.29'
NAIL & TAG IN SE SIDE 12" ASH S45°W 67.66'



Signed by Raymond Moored

Date 10/25/95

Surveyor's Michigan License No. 26463