

APR 08 1996

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

Nov 8 10 48 AM '95

COMMISSION BARR COUNTY REMONUMENTATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY (County) Located In: _____ Corner Code #/ # _____

1. Public Land Survey T _____ R _____
T4N _____ R7W _____ K-9

SEC. CORNER COMMON TO SEC'S 23,24,25,26
WOODLAND TWP T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sandy Schondelmayer
REGISTER OF DEEDS

002308

Register of Deeds Stamp & File Number

I, RAYMOND MOORED, in a field survey on 24 SEPT, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration.

GENERAL LAND OFFICE S. SIBLEY, D.S., 1830(R7W, P.133) BEECH 6 S19E 17/ BEECH 7 N37W 13 1/2 BOWEN 10-1875, FOUND STONE AND BRICK (NO WITS) (L.1, PG. 92)
CO. RD. COMM WITS- MDOT FOUND POINTED STONE
SW COR FNDN WALL TO CHURCH N39E 60.59' SW COR FNDN WALL TO CHURCH N39E 60.59'
15" CATALPA S51W 69.76' 15" CATALPA S51W 69.76'
24" MAPLE S77W 66.40' 24" MAPLE S77W 66.40'
12" MAPLE SW 58'
SW COR CHURCH NE 65.7

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE IN MON. BOX PER MDOT INFORMATION
NO WITNESSES REMAINED. DISTANCE TO WEST 1/4 CORNER (K-8) MATCHED MDOT STATIONING.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
JULY 10, 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
-NAIL & TAG IN FISHING SIGN POST S60°E 163.61'
-NAIL & TAG IN CUT OFF POWER POLE W/ CABLE BOX N85°E 177.42'
-NAIL & TAG IN POWER POLE W/ CABLE BOX N70°W 179.90'
-RR SPIKE IN POWER POLE S80°E 125.89'



Signed by Raymond Moored Date 10/25/95
Surveyor's Michigan License No. 26463