

MAY 20 1997

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED

DEC 9 2 11 PM '96

Sandy S. Reinholdmeyer REGISTER OF DEEDS

Form with fields: For Corners in BARRY, Located In: T.4N R.7W ...K-13, 1. Public Land Survey SEC COR COMMON SEC. 35 & 36 WOODLAND TWP., 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims.

002452

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, RAYMOND MOORED, in a field survey on MAY, 1994 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO L. LYON D.S. 1826 (R7W,P.122) ASH 18 N.25 1/2 E 4 DO. 6. N32W. 16. BOWEN 25-28 MARCH 1878 (L.1.P.229) SET STAKE, STONE, & BRICK. COUNTY ROAD COMMISSION CORNER TO CASTLETON & WOODLAND TWP'S. (COVERT ROAD PLANS, LP.11 NO DATE) (1920 #577 NASHVILLE RD. FO,P.14) 8" MAPLE SW 61.8' TWIN WILLOW W. 31.4' 40.1' EAST OF CENTERLINE SOUTH. 8" CHERRY N79DEG.E 83.97' 21" MAPLE S20DEG E 61.93' 16" ELM S 55 DEG. W 60.20' 53.1' E. OF CAST. CORNER(P.17, BOUND RODD COMM. SURVEY) 8" APPLE 61.8' SW DOUBLE WILLOW 31.4'W 40.1' EAST OF CASTLETON TWP. COR. MDOT/MDNR KK(1957 HIGHWAY PLANS, 1.12) CORNER COMMON TO SEC'S 1,2,36 & 35

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON PER MDOT INFORMATION STATED ABOVE. ACCEPTED AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-NAIL & TAG IN E SIDE 30" MAPLE SOUTH 159.39'
-NAIL & TAG IN E SIDE 30" MAPLE S25°E 91.56'
-NORTH COR OF CONC RW POST S65°E 83.13'
-NE COR SEC. 2 (K-1) WEST 53.10'
-C/L M-66 WEST 40.1'



Signed by Raymond Moored

Date 12/2/96

Surveyor's Michigan License No. 26463

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 13 NOV. '95 BRIAN REYNOLDS COUNTY SURVEYOR