

FEB 0 8 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

1. Public Land Survey T 4N R 7W L-3
1/4 CORNER COMMON TO T _____ R _____
SECTIONS 1 & 12 T _____ R _____
WOODLAND TOWNSHIP T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____



2699
Page: 1 of 1
11/25/1998 12:13P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 10 DECEMBER, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S. 1830, (R&W,P.136) "WEST CORRECTED 40.27" BEECH 12 S85E 4 LYNN 5 N69W 4
- COUNTY SURVEYOR RECORDS: WALTER HEATH, APRIL 18-19, 1905 (L.3,P.102) "DUG & FOUND STONE IN HIGHWAY" MAPLE 10 S52E 66 1/4 HICKORY 8 N55 3/4E 80
- CHICAGO, KALAMAZOO, & SAGINAW RAILROAD, 8 NOV., 1888 (L.1 OF PLATS, P.34) "261' EAST OF CHICAGO, KALAMAZOO, & SAGINAW RAILROAD"
- MDOT HIGHWAY PLANS FOR M-50. DATED 1922 INDICATE SUBJECT CORNER AT STATION 2867+00 DEFLECTION 0°8'LT. SAME PLANS INDICAT M 3 AT STATION 0+00 (SHOWN AS COMMON CORNER), "1/8 CORNER" AT STATION 13+32.5 DEFLECTION 0°21'RT, K-3 AT STATION 53+37.4 DEFLECTION 1°10'LT. MONUMENT NOT DESCRIBED.
- PRIVATE NOTES OF SURVEY BY BRIAN REYNOLDS, P.S. #31602, SURVEY IN SECTION 1 OF WOODLAND TWP., DATED JULY 27, 1996, NO MONUMENT FOUND, MDOT DISTANCE FROM K-3 TO M-3 5337.4 MEASURED 5337.77, COMPUTED CENTERLINE BETWEEN K-3 AND M-3 INCLUDING DEFLECTIONS, SET CORNER AT COMPUTED POSITION.

N & T IN W SIDE U. POLE N04°E 56.28' N & T IN E SIDE U. NW 24" TRUNK TRIPLE ELM N02°W 149.65'
N & T IN S SIDE U. POLE N79°E 236.83' 0.5' SOUTH OF EXISTING CENTERLINE

6. NOTE: AFTER APPROVAL OF THE CORNER POSITION BY THE BARRY COUNTY PEER GROUP AND PRIOR TO THE SETTING OF THE MONUMENT, LCRC #501 WAS FILED BY ROBERT A. LIIMAKKA, P.S. #40161, 5 MAR, 1997, WITH THE FOLLOWING:

- (PART B) FOUND P.K. NAIL 0.5' SOUTH OF M-50 (PART C) SET MONUMENT AND IRON PIN. (FOR MONUMENT PRESERVATION)
N60°E 79.78' SPIKE IN POWER POLE N38°W 75.75' IRON FENCE RAIL (BACK/BASE)
N&T IN WEST SIDE OF UTILITY POLE N04°E 56.28' N&T IN SOUTH SIDE UTILITY POLE N79°E 236.83'
0.5' SOUTH OF EXISTING CENTERLINE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER WAS RESTORED AS DESCRIBED IN ITEM #5 ABOVE. METHOD OF RESTORATION AND CORNER POSITION WERE APPROVED BY BARRY COUNTY PEER GROUP. FOUND IRON IN MON BOX AS DESCRIBED IN ITEM #6 ABOVE. REPLACED FOUND IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP IN MON. BOX.
FOUND NAIL W/PLASTIC TAG IN THE OSOUTH SIDE OF A UTILITY POLE N79°E 236.83'
SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A UTILITY POLE N68°W 372.57'
20d NAIL W/PLASTICTAG IN THE WEST SIDE OF A UTILITY POLE N04°E 56.28'
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 6" MAPLE CLUSTER NN02°W 152.24'
CENTERLINE OF AN EAST-WEST BITUMINOUS ROADWAY LIES NORTH 0.5'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

10 July 95 BR
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date Nov 24, 1998