

APR 08 1996

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

NOV 8 10 48 AM '95

Sandy Schondelmar
REGISTER OF DEEDS

002309

Register of Deeds Stamp & File Number

For corners in
BARRY

(County)

Located In:

Corner Code #/

- | | | |
|--|---------|-----|
| 1. Public Land Survey
CENTER 1/4 COR.
SECTION-24,
WOODLAND TWP. | T4N R7W | L-8 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling
in Section | S T R | |
| | S T R | |
| 3. Miscellaneous
Property in Sec. | S T R | |
| | S T R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RAYMOND MOORED 24 SEPT. 94

I, RAYMOND MOORED, in a field survey on 24 SEPT. 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO-CORNER NOT SET BY GLO
CO. SURVEYOR LEE COBB, APRIL 7,8,9, 1909 SET STONE IN PIT OF STONES (NO WITS)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
DUG FOR STONES AT INTERSECTION OF FENCES NORTH, SOUTH, AND WEST.
DID NOT FIND STONE OR PIT OF STONES. DISTANCE FROM FENCE INTERSECTION TO WEST 1/4 (K-8) MATCHED WITHIN 1 FOOT. ACCEPTED FENCE INTERSECTION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN BASE OF ROTTED CORNER FENCE POST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.
-NAIL & TAG IN EAST SIDE FENCE POST SOUTH 4.05'
-NAIL & TAG IN SOUTH SIDE 18" BEECH N85°E 9.25'
-NAIL & TAG IN WEST SIDE 24" BEECH N10°E 18.87'
-NAIL & TAG IN SOUTH SIDE 6" MAPLE N80°W 21.24'
-FACE 24" BEECH S5°E 12.9'
-IN LINE WITH FENCES NORTH, SOUTH, WEST

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
JULY 10, 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 10/25/95