

APR 08 1996

COMMISSION

BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

Nov 8 10 48 AM '95

Sandy Schindelmayr  
REGISTER OF DEEDS

002305

Other #1

Register of Deeds Stamp & File Number

For corners in  
BARRY

(County)

Located In:

Corner Code #/

- 1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S 24 T 4N R 7W  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RAYMOND MOORED

24 AUG.

94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration.

GLO - SET BY GLO DEPUTY SURVEYOR SYLVESTER SIBLEY, SEE BELOW FOR WITNESSES.  
COBB CIRCA 1900 SET STONE AND BRICK FOR MEANDER CORNER ON SECTION LINE 38.5 CHAINS EAST OF THE SOUTHWEST CORNER OF SECTION.  
COBB - APRIL 7, 8, 9, 1909 FOUND STONE AND BRICK FROM FORMER SURVEY (L-1, PG. 355)

GENERAL LAND OFFICE NOTES ..40.30 CORNER IN LAKE 42.11 SET P. ON W. SIDE OF LAKE  
A. W. OAK 16 S29W 33  
DO. 6 N45 1/2W 36  
80.61 SECTION CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND VERY LARGE POINTED STONE AND 3/4" X 2" IRON BAR WITH LOOP ON END NEXT TO STONE IN OLD EAST AND WEST FENCE LINE. DISTANCE FROM SW CORNER OF SECTION WAS 2.72 FEET LONGER THAN COBB IN 1909. ATTEMPTS TO EXCAVATE STONE AND BAR WERE UNSUCCESSFUL. LEFT FOUND ACCESSORIES IN PLACE AND ACCEPTED STONE AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
JULY 10, 1995 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LARGE POINTED STONE WITH 3/4" X 2" BAR WITH LOOP ON END NEXT TO STONE  
-NAIL IN NORTH SIDE 8" OAK DUE WEST 16.43'  
-NAIL IN SW SIDE 30" OAK N50°W 19.15'  
-NAIL IN EAST SIDE 6" MAPLE S10°W 30.43'  
-NAIL IN TRUNK OF OAK CLUSTER DUE EAST 24.96'  
-SHORE OF LAKE DUE EAST 35' +/-



Signed by Raymond Moored

Date 11/1/95

Surveyor's Michigan License No. 26463