

SURVEY &
REMONUMENTATION
OCT 27 1994
COMMISSION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

OCT 7 2 04 PM '94

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmar
REGISTER OF DEEDS

002234

For corners in
BARRY
(County)

Located in: Corner Code =#

1. Public Land Survey	T <u>4N</u> R <u>8W</u>	<u>A-6</u>
CARLTON TOWNSHIP	T _____ R _____	_____
W 1/4 COR SEC 18	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **BRIAN REYNOLDS**, in a field survey on 12 JULY, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. **NOT SET BY GENERAL LAND OFFICE. NO HISTORICAL DATA OF RECORD COULD BE FOUND FOR THIS CORNER.**
- 2. **SURVEY OF SECTION 18, c. 1992, BY BURT WICKHAM, P.S. #17639, PRIVATE NOTES READ, "SET 1/2" RE-ROD ON LINE BETWEEN NE CORNER SECTION 13-4N-9W (BRANT CAPPED IRON) AND E 1/4 CORNER SECTION 13-4N-9W (NEDERVELD CAPPED IRON) EQUIDISTANT FROM NW CORNER SECTION 18-4N-8W (BRANT CAPPED IRON) AND FENCE LINE RUNNING EAST AT SW CORNER OF SECTION 18-4N-8W"**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 1/2" IRON AND WITNESSES BY WICKHAM. TRAVERSE OF SECTION 18 CONFORMED WITH BEARINGS AND DISTANCES BY WICKHAM. POSITION IS CONSISTANT WITH OCCUPATION EAST. ACCEPTED IRON BY WICKHAM AS A PROPER RESTORATION OF CORNER PROBABLY SET IN THE COURSE OF A SURVEY (NOT OF RECORD) MANY YEARS AGO.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
2 AUGUST, 1994
12 SEPT. 1994
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON (3/4"X36"W/ALUMINUM CAP)

FOUND NAIL IN NE SIDE OF A 10" HICKORY S45E 18.76'
FOUND NAIL IN NE SIDE OF AN 8" ASH N45W 28.22'
SET 40d NAIL W/REMON TAG IN NW SIDE OF A 12" HICKORY N39E 38.32'
SET 40d NAIL W/REMON TAG IN E SIDE OF AN 18" QUAD OAK N4W 87.62'



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date OCT 7, 1994