

OCT 27 1994

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD  
SEP 26 11 21 AM '94

Sandy Schindelmarper  
REGISTER OF DEEDS

002219

For corners in  
**BARRY**  
(County)

Located In:	Corner Code #:
T <u>4N</u> R <u>8W</u>	<u>A-9</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling in Section: S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec. S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

1. Public Land Survey  
**CARLTON TOWNSHIP  
SW COR SECTION 19**

2. Property Controlling in Section: S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

**BRIAN REYNOLDS** in a field survey on **12 JULY**, 19 **94**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. **GENERAL LAND OFFICE: SYLVESTER SIBLEY D.S., c. 1830**  
"WEST 77.91 WEST BOUNDARY 32 LINKS NORTH OF POST  
A. BEECH 12 N35E 18  
A. WHITE OAK 7 S21E 30

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
2 Aug. '94 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

2. **COUNTY SURVEYOR RECORDS: A.D. RORK, DECEMBER 7, 1866, (LIBER 2 OF SURVEYS PAGE 120) "FOUND BEARINGS"**

3. **NO OTHER HISTORICAL DATA, PUBLIC OR PRIVATE, COULD BE FOUND.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**IT APPEARS THAT THE DISTANCE DATA RECITED IN THE GENERAL LAND OFFICE NOTES ARE GROSSLY IN ERROR, AS TO BOTH THE CLOSING DISTANCE AND THE FALLING BETWEEN STANDARD AND CLOSING CORNERS (CLOSING 1/2 MILE 2502.06' GLO, 2391.49' MEASURED; FALLING 21.12' GLO, 82.46' MEASURED) FOUND IRON FOR M-9, T4N R9W. CONDUCTED EXTENSIVE SEARCH FOR CORNER EVIDENCE FOR A-9 AND FOUND NOTHING. INTERSECTED THE PROJECTED LINE FROM C-9 THROUGH B-9 WITH THE RANGE LINE DEFINED BY M-9 AND M-8. T4N R9W. THIS POSITION IS CONSISTENT WITH OCCUPATION LINES FOR 1/4 LINE AND 1/8 LINE. THIS IS THE METHOD THAT SHOULD HAVE BEEN, BUT APPARENTLY WAS NOT, FOLLOWED BY THE GLO DEPUTY SURVEYOR. THE EXISTENCE OF OCCUPATION LINES CONSISTENT WITH THIS POSITION INDICATE THAT SURVEYS (NOT OF RECORD) MANY YEARS AGO USED THE SAME METHOD.**

**ACCEPTED THIS METHOD OF RESTORATION AS THE BEST POSSIBLE WAY TO RESTORE THE CORNER PROBABLY NEVER SET BY THE GLO DEPUTY SURVEYOR**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**SET STANDARD BARRY COUNTY REMONUMENTATION IRON (3/4"X36"W/ALUMINUM CAP)**

- SET 40d NAIL W/REMON TAG IN N SIDE OF AN 18" OAK S86W 61.69'
- SET 40d NAIL W/REMON TAG IN N SIDE OF A UTILITY POLE S74W 41.32'
- SET 40d NAIL W/REMON TAG IN NE SIDE OF A UTILITY POLE S56E 65.87'
- SET 40d NAIL W/REMON TAG IN THE TOP OF A WOODEN FENCE POST S27E 48.94'
- CORNER LIES ROUGHLY IN CENTER OF GRAVEL ROAD ( FIGHTER RD. )



Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date SEPT 23, 1994