

OCT 27 1994

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

SEP 26 11 21 AM '94

Sandy Schondelmaier
REGISTER OF DEEDS

For corners in

BARRY

(County)

Located in:

4N 8W

Corner Code #

B-5

1. Public Land Survey
CARLTON TOWNSHIP
N 1/4 COR SECTION 18

T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

002220

Register of Deeds Stamp & File Number

I, BRIAN REYNOLDS, in a field survey on 12 JULY, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE : SYLVESTER SIBLEY D.S., DECEMBER 1830.
- A. MAPLE S S61E 78 - A. HICKORY 7 N5W 84
- COUNTY SURVEYOR NOTES: NO NAME OR DATE (LIBER 1 OF SURVEYS, PAGE 273)
"IRON AND CROCKERY FOR CORNER" BLACK ASH 10 S3 1/2W 83
- PRIVATE NOTES: BURT WICKHAM, P.S. #17639, SURVEY OF SECTION 18, c. 1992
"FOUND 1/2" CAPPED REROD FLUSH WITH ROAD SURFACE"
WITS: NAIL IN 24" MAPLE CLUSTER S10E 25.62'
SOUTH END OF 48" OVAL CMP S10 W 34.30'
NORTH END OF 48" OVAL CMP N15W 43.76'
NAIL IN 8" ELM N60E 50.74'
TREE LINE NORTH
C/L BIT. ROAD NORTH 3.5'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
2 Aug. '94
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" CAPPED IRON RECITED BY WICKHAM, IDENTIFICATION ON CAP OBLITERATED. SEARCHED EXTENSIVELY FOR IRON, CROCKERY, AND WITNESSES FROM COUNTY SURVEYOR NOTES, NOTHING FOUND. IT IS LIKELY THAT THE IRON AND CROCKERY WERE DESTROYED IN THE COURSE OF INSTALLING THE 48" OVAL CMP CULVERT AS RECITED BY WICKHAM.


ACCEPTED FOUND 1/2" IRON AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.

REPLACED 1/2" IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT IN MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON (3/4"X36" W/ALUMINUM CAP) AND INSTALLED MONUMENT BOX

- SET 40d NAIL W/REMON TAG IN NW SIDE OF A 10" MAPLE S26W 41.17'
- SET 40d NAIL W/REMON TAG IN NW SIDE OF A 4" MAPLE S46E 38.44'
- FOUND 40d NAIL IN E SIDE OF A MAPLE CLUSTER S14E 25.70
- FOUND 40d NAIL IN SW SIDE OF A MAPLE CLUSTER N40W 41.37
- CORNER LIES 3.5' SOUTH OF C/L BITUMINOUS ROADWAY (SISSON ROAD)



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date SEPT 23, 1994