

OCT 27 1994

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

SEP 26 11 21 AM '94

Sandy Schindelmarper
REGISTER OF DEEDS

002222

Register of Deeds Stamp & File Number

For corners in
BARRY

(County)

Located In:

4N 8W

Corner Code #

B-8

- 1. Public Land Survey T R _____
CARLTON TOWNSHIP T R _____
CENTER SECTION 19 T R _____
 T R _____
- 2. Property Controlling S T R _____
in Section S T R _____
- 3. Miscellaneous S T R _____
Property in Sec. S T R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, **BRIAN REYNOLDS** in a field survey on **12 JULY**, 19 **94**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	●	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1. **CORNER NOT SET BY GENERAL LAND OFFICE.**
- 2. **NO HISTORICAL DATA COULD BE FOUND FOR THIS CORNER. NOTHING IN ROAD COMMISSION OR COUNTY SURVEYOR NOTES.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND INTERSECTION OF DECAYED FENCES SOUTH AND EAST. CONDUCTED EXTENSIVE SEARCH FOR MONUMENTATION AND FOUND NOTHING.

PLACED STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT INTERSECTION OF 1/4 LINES AS DEFINED BY RESTORED 1/4 CORNERS. POSITION FIT INTERSECTION OF FENCES VERY WELL.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

2 Aug. 94
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON (3/4"X36" W/ALUMINUM CAP)

- SET 40d NAIL W/REMON TAG IN NE SIDE OF A 14" TRIPLE POPLAR N75W 6.00'
- SET 40d NAIL W/REMON TAG IN NW SIDE OF A 3" HICKORY N50E 13.17'
- SET 40d NAIL W/REMON TAG IN SW SIDE OF A 10" TRIPLE POPLAR S75E 2.82'
- SET 40d NAIL W/REMON TAG IN NW SIDE OF A 6" HICKORY N30E 2.80'
- IN LINE WITH DECAYED FENCE TO THE EAST
- IN LINE WITH DECAYED FENCE TO THE SOUTH



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date SEPT 23 1994