

OCT 27 1994

COMMISSION

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

SEP 26 11 21 AM '94

Sandy Schendelmayer
REGISTER OF DEEDS

For corners in

BARRY

(County)

Located In:

Corner Code #

- | | | | | | |
|-------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>8W</u> | <u>C-9</u> |
| CARLTON TOWNSHIP | T | _____ | R | _____ | _____ |
| SE COR SEC 19 | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling | S | _____ | T | _____ | _____ |
| in Section | S | _____ | T | _____ | _____ |
| 3. Miscellaneous | S | _____ | T | _____ | _____ |
| Property in Sec. | S | _____ | T | _____ | _____ |

002228

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **BRIAN REYNOLDS**, in a field survey on 9 SEPT, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: SYLVESTER SIBLEY D.S., 1830 (R8W, Pg. 164)
A. TAMERACK 15 S40E 5 1/2
Do. 18 S73 1/2W 11 1/2
- COUNTY SURVEYOR RECORDS: FRANK S. BOWEN, 22 MARCH 1878; STONE FOR CORNER (LIBER 1 OF SURVEYS, PAGE 227).
- COUNTY ROAD COMMISSION: CROCKERY IN MONUMENT BOX (NO NAME OR DATE)
E27 HUB (20" ELM SW 28.58') ?
W27 HUB (24" MAPLE SE 31.3') ?
- MICHIGAN STATE HIGHWAY DEPARTMENT: J.L. CORBIT PARTY, 1957 MSHD 08012 M-43 1957, (V.F. Pg.11) CONSUMERS POWER COMPANY.
BOATSPIKE RESET FROM WITNESSES,
8"-14" TWIN ELM S68.30W 43.85'
TELEPHONE POLE N77W 105.90'
POWER POLE S88E 47.42'
- NO OTHER RECORDED HISTORICAL INFORMATION FOR THIS CORNER COULD BE FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" BOATSPIKE IN MONUMENT BOX.

ACCEPTED FOUND 3/4" BOATSPIKE AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.

REPLACED 3/4" BOATSPIKE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT IN MONUMENT BOX.


ALL BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

2 Aug. '94
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON (3/4"X36"W/ALUMINUM CAP)

- SET 40d NAIL W/REMON TAG IN NW SIDE OF A UTILITY POLE S28E 134.96'
- SET 40d NAIL W/REMON TAG IN TOP CENTER OF A GUARD RAIL POST S30E 39.42'
- SET 40d NAIL W/REMON TAG IN TOP CENTER OF A GUARD RAIL POST N30E 40.05'
- SET 40d NAIL W/REMON TAG IN TOP CENTER OF A GUARD RAIL ANCHOR POST N19W 76.81'
- CORNER LIES ON C/L OF HIGHWAY M-43
- CORNER IS IN LINE WITH TREE LINE TO THE WEST



Signed by

[Signature]

Date

SEPT 23, 1994

Surveyor's Michigan License No.

31602