

BARRY COUNTY REMONUMENTATION

APR 04 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in Located In: Corner Code #
BARRY (county)

1. Public Land Survey T 4N R 8W C-11
CORNER COMMON TO T R
SECTIONS 29, 30, 31, & 32 T R
CARLTON TOWNSHIP T R

Barcode with number 2766, Page: 1 of 05/18/1999 02:1, Sandy Schondelmayer- Barry Co. LCRCR

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No, Recorded Plat

5. Private Claims

I, Brian Reynolds, in a field survey on 10 AUGUST, 1990 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R8W, P.162): A. B. OAK 30 S16E 59 A. W. OAK 32 N45W 39
2. COUNTY SURVEYOR WALTER HEATH, APRIL 25-28 1903 (L.3, P.86): "FOUND STONE EMBEDDED IN ROAD" NE CORNER OF SCHOOL HOUSE S80 1/2 W 95 lks SW CORNER CHURCH N26 1/2 E
3. COUNTY ROAD COMMISSION: NO NAME OR DATE: "1" PIPE" 20" POPLAR NE 66.80' COR. F P SE 31.80' 8" MAPLE SW 67.55' ALSO: NO NAME 7-15-71 FIELD NOTES: "MONUMENT BOX IN M-43"
4. HIGHWAY DEPARTMENT: J.L. CORBIT PARTY, 1957, (PROJECT 08012) "FOUND GAS PIPE FROM OLD WITNESSES" 8.66' Lt OF STA. 963+74.31 NE CORN OLD SCHOOL S82 W 61.92' SE COR GRANGE HALL N57 W 60.85' SW COR CHURCH N27 30 E 102.54'
5. ACT 132 SURVEY: BY Wm. HUME ROGERS, P.S., #6197 (L.1, P.3), OCT. 25, 1971: "MONUMENT BOX AT S.W. CORNER OF SECTION 29, T4N, R8W" NO WITNESSES GIVEN.
6. PLAT OF "WELCOME ACRES No. 1": BY ROY F. DeHAVEN, RPCE #3026 17 NOV. 1971 (LIBER 5 OF PLATS, PAGE 83) NO WITNESSES GIVEN
7. PRIVATE NOTES OF SURVEY: BY JAMES L. KING, P.S. #14766, JOB #86003: "WITNESSES TO 1/4" IRON" SAME AS IN #3 ABOVE
8. LAND CORNER RECORDATION CERTIFICATE: #417, BY BRIAN REYNOLDS, P.S. #31602, 7 MARCH, 1990: "FOUND 1/4" IRON IN MONUMENT BOX. DISTANCE TO C-12 COMPARES FAVORABLY WITH HEATH SURVEY AND MDOT STATIONING." FOUND NAIL & SHINER IN SE COR OLD CHURCH N55 W 60.80' Fd. OLD N & S IN U-POLE S25 W 124.42'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND BOAT SPIKE IN MONUMENT BOX & WITNESSES IN #7 & #8 ABOVE. ACCEPTED AS BEST EVIDENCE OF CORNER POSITIC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 28" OAK N78 E 195.27' SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A UTILITY POLE S65 E 172.83' SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 24" MAPLE N25 W 127.10' FOUND NAIL W/SHINER IN THE WEST SIDE OF A UTILITY POLE S20 W 124.36' NORTHEAST FOUNDATION CORNER OF RESIDENCE N42 W 77.59' 8.5' +/- WEST OF PAINTED NORTH-SOUTH CENTERLINE 1' +/- SOUTH OF PAINTED CENTERLINE EAST

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 Jan '98 BRIAN REYNOLDS COUNTY SURVEYOR

Signed by Surveyor's Michigan License No 31602

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a dot in cell 11C.

Register of Deeds Stamp & File Number



Date MAY 18, 1999