

REVISIONS

APR 04 2000

SECTION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in BARRY (county) Located In: Corner Code #

1. Public Land Survey 1/4 CORNER COMMON TO SECTIONS 29 & 32 CARLTON TOWNSHIP T 4N R 8W D-11

2. Property Controlling in Section S T R

3. Miscellaneous Property in Sec. S T R

4. Lot No, Recorded Plat

5. Private Claims

I, Brian Reynolds, in a field survey on 10 AUGUST, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830, "A. W. OAK 12 INCHES IN PLACE FOR 1/4 SECTION CORNER"
2. MDOT: J.L. CORBIT, 1957, SURVEY OF M-43: "FENCE CORNER AT DOUBLE DISTANCE TO 1/8 LINE FENCE FROM NW CORNE
3. LCRC #8, Wm. HUME ROGERS, P.S.#6197, OCT. 25, 1971, PARTS A & B BLANK, PART C: "12" ASH DUE WEST 7.5' TO SPIKE 14" HICKORY S85°E 21.0' 16" OAK N45°W 14.0' TO SPIKE IN WEST SIDE. 1/2" IRON PIPE AT FENCE CORNER"
4. ACT 132 SURVEY, L. 1, P. 3, BY Wm. HUME ROGERS, P.S.#6197, OCTOBER 25, 1971, SAME AS ITEM #3 ABOVE
5. COUNTY ROAD COMMISSION: SAME WITNESSES AND DATE AS LCRC#8 ABOVE
6. UNRECORDED SURVEY BY BRIAN REYNOLDS, P.S. #31602, 29 APRIL 1991, "WITNESSES TO 1/2" PIPE 20" HICKORY S85°E 20.67' 14" ELM N41°E 61.31' 6" ELM N31°E 44.88' IN FENCE EAST"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 1/2" PIPE AT FENCE CORNER AS RECITED IN ITEMS 3-6 ABOVE. ACCEPTED AS BEST AVAILABLE EVIDENCE OF CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A WOOD CORNER POST WEST 0.46' FOUND 60d NAIL IN THE NORTHWEST SIDE OF A 5" MAPLE N45°E 1.95' FOUND 60d NAIL IN THE NORTH SIDE OF A 6" ELM S45°E FOUND 60d NAIL IN THE NORTH SIDE OF A 20" HICKORY S85°E 20.67' IN LINE WITH FENCE EAST UNDER A FENCE CORNER POST LEANING EASTERLY

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 Jan. '98 BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature] Surveyor's Michigan License No 31602

Date MAY 13, 1999

Barcode with number 2768, Page: 1 of 05/18/1999 02:5, Sandy Schondelmayer - Barry Co. LCRCR, Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13, containing numbers 1-36 and a dot in cell 11,32.