

AUG 13 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in Located In: Corner Code #  
**BARRY** (county)



2684  
Page: 1 of 1  
04/23/1998 08:10A

1. Public Land Survey T 4N R 8W G-10  
1/4 CORNER COMMON TO T \_\_\_\_\_ R \_\_\_\_\_  
SECTIONS 27 & 28 T \_\_\_\_\_ R \_\_\_\_\_  
CARLTON TOWNSHIP T \_\_\_\_\_ R \_\_\_\_\_

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, **Brian Reynolds**, in a field survey on **23 JUNE, 1997** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R8W, P.154) A. BOXWOOD 7 N84E 18 AN IRONWOOD 6 S59 1/2W 39
- 2. COUNTY SURVEYOR RECORDS: F. BOWEN, 1877, (BR. CARLTON F.B., P.70) W. OAK STUMP 30 N52 1/2W 48 B. OAK 12 S29W 42

\*\*\* NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER \*\*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO LOCAL EVIDENCE OF MONUMENTATION. TRAVERSED ENTIRE EAST 1/2 OF SECTION 28, ALONG WITH THE WEST 1/4 CORNER. FOUND THAT PROJECTION OF LINE FROM WEST 1/4 CORNER THROUGH FENCE OCCUPATION NEAR CENTER OF SECTION FALLS APPROXIMATELY ON CENTERLINE OF GRAVEL ROAD AT G-10. ALSO FOUND THAT FENCE OCCUPATION 1/4 MILE SOUTH OF G-10 FALLS ON A LINE FROM G-9 TO G-11. INTERSECTED LINE FROM G-9 TO G-11 WITH LINE FROM WEST 1/4 CORNER THROUGH FENCE OCCUPATION NEAR CENTER. CORNER POSITION THUS ESTABLISHED AGREES WELL WITH 1/8 LINE OCCUPATION EAST-WEST THROUGH THE SOUTHEAST 1/4. ROAD SURFACE AT COMPUTED LOCATION APPEARS TO BE A SLIGHT CUT. EXCAVATION AT COMPUTED LOCATION THROUGH THIN GRAVEL GRADE INTO CLAY, PROBED THROUGH CLAY, FOUND NO EVIDENCE OF MONUMENTATION. ACCEPTED COMPUTED POSITION AS PROPER RESTORATION OF CORNER POSITION BASED ON AVAILABLE EVIDENCE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A UTILITY POLE N6°E 114.83'
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A UTILITY POLE N36°E 145.19'
- SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A WOOD POST N34°E 28.46'
- SET 20d NAIL W/REMON TAG IN THE SOUTHWEST SIDE OF A 4" BLACK WALNUT S57°E 46.56'
- CORNER IS ROUGHLY ON CENTERLINE OF AN EAST-WEST GRAVEL ROAD ON EXTENDED CENTERLINE OF GRAVEL DRIVE NORTH

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

14 July '97 ISR  
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]  
Surveyor's Michigan License No 31602

Date APRIL 20, 1998