

FEB 03 1999

BARRY COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in
BARRY
(county)

Located In:

Corner Code #



2690

Page: 1 of 1
10/26/1998 10:57A

Sandy Schondelmayer - Barry Co. LGRCR

- 1. Public Land Survey
CORNER COMMON TO
SECTIONS 27, 28, 33, & 34
CARLTON TOWNSHIP
T 4N R 8W G-11
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling
in Section: S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous
Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 1 MAY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R8W,P.153) A. W. OAK 8 N73E 4 Do. 22 S5W 20
 2. COUNTY SURVEYOR RECORDS: FRANK BOWEN, 16-17 FEB., 1877 (L.1,P.184) "U.S. BEARINGS"

*** NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. FOUND OLD WOODEN ANCHOR FENCE POST, DETERIORATED AND LEANING NORTH AT INTERSECTION OF OLD TREE AND FENCE LINE WEST WITH FENCE AND TREE LINE NORTH, TREE LINE ONLY SOUTH. EXCAVATED AND FOUND ROTTED BASE OF OLDER CORNER FENCE POST, SURROUNDED BY STONES. ACCEPTED ROTTED FENCE POST AND STONES AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT IN CENTER OF OLD ROTTED WOOD FENCE POST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A 45" OAK S89°W 97.18'
- SET 20d NAIL W/REMON TAG IN THE SOUTHEAST SIDE OF A 10" OAK S76°W 21.65'
- SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 30" OAK N75°E 74.99'
- SET 20d NAIL W/REMON TAG IN THE EAST ROOT OF A 30" MAPLE N02°E 9.86'
- SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A UTILITY POLE S17°W 110.95'
- NORTHEAST CORNER OF A HOUSE (ATTACHED GARAGE) S33°E 152.23'
- IN LINE WITH OLD LARGE TREE/FENCE ROW WEST AND NORTH, TREE ROW SOUTH.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

14 July 97 BR
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date APRIL 20, 1998