

FEB 03 1999


LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in
BARRY
(county)

Located In:

Corner Code #



Sandy Schondelmayer - Barry Co. LCRCR

2691

Page: 1 of 1
10/26/1998 10:57A

1. Public Land Survey
CORNER COMMON TO
SECTIONS 33 & 34
CARLTON TOWNSHIP
ON TOWNSHIP LINE

T 4N R 8W G-12
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

4. Lot No _____ Recorded Plat _____
5. Private Claims _____

I, Brian Reynolds, in a field survey on 10 AUGUST, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.
NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R8W, P.153) A BEECH 17 N32E 24 Do. 7 S32W 25
- COUNTY SURVEYOR RECORDS: FRANK S. BOWEN, JAN. 1878 (L.1,P.219) "FOUND U.S. BEARINGS, TOOK NEW ONE" BEECH 12 S62W 51
- LAND CORNER RECORDATION CERTIFICATE:#69 BY HAROLD W. DORCEY, P.S. #9429, 2 JAN. 1973, "FOUND 1/2" PINCHED PIPE PLAT MON. 33FEET EAST AND 33 FEET WEST" (NO WITNESSES GIVEN)
- COUNTY ROAD COMMISSION: NO NAME 1 JANUARY, 1973, "IRON" PLAT MONUMENT 33' EAST PLAT MONUMENT 33' WEST
- RECORDED PLAT OF LOWER LAKE SUBDIVISION, BY ORVAL CUTSHAW Jr., P.E. #8677. (L. 5 OF PLATS, PAGE 40) REFERENCED, NO WITNESSES
- PRIVATE NOTES: CONSUMERS POWER, FROM DORCEY #3 ABOVE
- PRIVATE NOTES: BRIAN REYNOLDS, P.S. #31602, 1 MAY 1996 "1" PIPE" N&T N SIDE 18" OAK S65°W 45.62'
N&T N.W. SIDE 15" BEECH S40°W 73.22' N&T W SIDE 7" MAPLE S25°E 80.08' N&T NE SIDE 7" MAPLE S46°E 82.24'
SE CORNER MTL. BLD. N42°W 98.92' CONC. MONUMENT EAST 32.77'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
ACCEPTED FOUND 1" PIPE AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.


WE WERE UNABLE TO REMOVE 1" PIPE.

LEFT FOUND 1" PIPE IN PLACE.

SET STANDARD BARRY COUNTY REMONUMENTATION ALUMINUM CAP ON TOP OF FOUND PIPE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION ALUMINUM CAP ON TOP OF FOUND PIPE.
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 18" OAK S65°W 45.62'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A 15" BEECH S40°W 73.22'
SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 7" MAPLE S25°E 80.08'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 7" MAPLE S46°E 82.24'
SOUTHEAST CORNER OF A METAL BUILDING N42°W 98.92'
CONCRETE MONUMENT EAST 32.77'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
14 July, 97
BRIAN REYNOLDS
COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No 31602

Date 10/19/1998