

SURVEY & REMONUMENTATION

FEB 17 1998



2640 Page: 1 of 1 12/16/1997 12:15P

Sandy Schondelmayer - Barry Co. LCRCR

SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich P.A. 1970

For Corners in BARRY COUNTY Located In: Corner Code #
1. Public Land Survey 1/4 COR COMMON TO SEC'S 26 & 27 CARLTON TWP. T..4N R..8W ....I-10.....
2. Property Controlling in Section S.....T..... R.....
3. Miscellaneous Property in Sec. S..... T..... R.....
4. Lot No....., Recorded Plat.....
5. Private Claims.....

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is present at row 10, column J.

I, RAYMOND MOORED, in a field survey on MAY 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: GLO: SYLVESTER SIBLEY D.S. 1830 (R8W, P.149) BEECH 7. S .19. E. 29 BEECH 24. N. 42. E. 69. NO CORNER HISTORY AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND NO EVIDENCE OF ORIGINAL CORNER OR ACCESSORIES. ESTABLISHED CORNER POSITION MIDWAY AND ON LINE BETWEEN I-9 AND I-11. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACCEPTED POSTION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 8 July '96 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP -C/L E-W GRAVEL ROAD SOUTH 18'+/- -NAIL & TAG IN W SIDE 12" OAK N25E 33.99' -NAIL & TAG IN N SIDE 24" SHAGBARK HICKORY S45E 72.40' -NAIL & TAG IN E SIDE 10" BEECH S30W 42.65' -NAIL & TAG IN S SIDE 36" HICKORY N85W 94.93'

[Signature]

Date 12/11/97

Surveyor's Michigan License No. 26463

