

**SURVEY &
REMONUMENTATION**

FEB 17 1998

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION



2641
Page: 1 of 1
12/16/1997 12:15P

For Corners in
BARRY COUNTY

Located In: Corr

Sandy Schondelmayer - Barry Co. LCRCR

- 1. Public Land Survey T.4N R.8W I-11.....
SEC. COR COMMON T..... R.....
TO SEC'S 26, 27, 34, 35 T..... R.....
CARLTON TWP. T..... R.....
- 2. Property Controlling S.....T..... R.....
in Section S.....T..... R.....
- 3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
- 4. Lot No....., Recorded Plat.....
- 5. Private Claims.....

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, RAYMOND MOORED, in a field survey on MAY 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: SYLVESTER SIBLEY D.S. 1830 (R8W, P.148) BEECH 11. S84E 8; BEECH 22 N88W 35.
COUNTY SURVEYOR RECORDS: BOWNE 16 & 17 FEB. 1877 (L.1, P. 184) FOUND OLD STAKE HOLE BY ONE OLD BEARING NEARLY GONE. BEECH 30 S 59 W 33; BEECH 10 N87W 12 1/2.
COUNTY ROAD COMMISSION: FENCE N S E & W, CORNER (JAN 1, 1973).
LCRC: NO. 69. BY HAROLD W. DORCEY, P.S. CORNER IS FENCE CORNER, FENCES N,S,E, & W
HW DORCEY FB#415 C.P.CO. 1-73. SAME AS LCRC # 69 ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND FENCE CORNER POST PER LCRC # 69 ABOVE. FENCES RUNNING N, S, E, & W.
SET STANDARD BARRY COUNTY REMONUMENTATION IRON AND CAP AT BASE OF CORNER FENCE POST.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 8 July, 96 *BR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-AT BASE OF CORNER FENCE POST
-FENCES NORTH, SOUTH, EAST, WEST
-NAIL & TAG IN NW SIDE 30" CHERRY N45E 8.00'
-NAIL & TAG IN E SIDE 10" CHERRY N2W 14.43'
-NAIL & TAG IN E SIDE 6" BEECH N10W 22.46'
- NAIL IN BASE OF 36" TRIPLE OAK WEST 8.28'

Raymond Moored

Date 12/11/97

Surveyor's Michigan License No. 26463

