

~~SURVEY & REMONUMENTATION~~

AUG. 22 1995

COMMISSION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

MAR 20 10 55 AM '95

Sandy Schendelmayer  
REGISTER OF DEEDS

For corners in

BARRY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>4N</u>	R	<u>8W</u>	<u>J-3</u>
1/4 CORNER COMMON TO SECTIONS 2 & 11	T	_____	R	_____	_____
CARLTON TOWNSHIP	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____

002294

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3									●			
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BRIAN REYNOLDS, in a field survey on 15 APRIL, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R8W,P.152)  
SUGAR 12 S26W 22 BEECH 6 N30E 12  
NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**NO EVIDENCE OF CORNER MONUMENTATION FOUND. INTERSECTED 1/4 LINE OCCUPATION WITH LINE FROM FOUND I-3 TO RESTORED K-3. INTERSECTED POINT FALLS 0.24' EAST OF MID-POINT. ACCEPTED AS BEST EVIDENCE OF CORNER POSITION. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND INSTALLED MONUMENT BOX.**

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
3 May 94  
BRIAN REYNOLDS  
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP) IN MONUMENT BOX.  
SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A UTILITY POLE S2°W 91.28'  
SET 40d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 14" CHERRY S68°E 95.46'  
SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF AN 18" BLACK WALNUT N2°E 90.95'  
SOUTHEAST CORNER OF A CONCRETE PORCH N44°W 136.16'  
6.8' NORTH OF THE CENTERLINE OF EAST-WEST BITUMINOUS ROADWAY.**



Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date MARCH 17, 1995