

SURVEY & REMONUMENTATION

FEB 17 1998

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION



2638
Page: 1 of 1
12/16/1997 12:15P

For Corners in
BARRY COUNTY

Located In:

Co

Sandy Schonheimayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

- 1. Public Land Survey T..4N R..8WJ-10.....
CEN. 1/4 COR T..... R.....
TO SEC. 26 T..... R.....
CARLTON TWP. T..... R.....
- 2. Property Controlling S.....T..... R.....
in Section S.....T..... R.....
- 3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
- 4. Lot No....., Recorded Plat.....
- 5. Private Claims.....

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	25								
11													
12	31	32	33	34	35	36							
13													

I, **RAYMOND MOORED**, in a field survey on **MAY 8, 1996** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: CORNER NOT ESTABLISHED BY G.L.O.

NO OTHER CORNER HISTORY AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON AND CAP AT THE INTERSECTION OF THE NORTH - SOUTH AND EAST - WEST QUARTER LINES.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 8 July '96 *BR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-FENCE CORNER POST N13E 16.66'
-NAIL & TAG IN W SIDE 6" OAK N35E 6.46'
-NAIL & TAG IN W SIDE 8" HICKORY N35E 5.80'
-NAIL & TAG IN N SIDE OAK CLUSTER N60E 3.45'
- NAIL & TAG IN N SIDE 14" HICKORY N85W 41.95'

Raymond Moored Date 12/11/97

Surveyor's Michigan License No. 26463

