

FEB 17 1998

1

SECTION

BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970



2637  
Page: 1 of 1  
12/16/1997 12:15P

For Corners in  
BARRY COUNTY

Located In: Cor

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

- 1. Public Land Survey T.4N R.8W ....J-11.....  
1/4 COR COMMON T..... R.....  
TO SEC'S 26 & 35 T..... R.....  
CARLTON TWP. T..... R.....
- 2. Property Controlling S.....T..... R.....  
in Section S.....T..... R.....
- 3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....
- 4. Lot No....., Recorded Plat.....
- 5. Private Claims.....

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RAYMOND MOORED, in a field survey on MAY 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO: SYLVESTER SIBLEY D.S. 1830 (R8W, P. 148 & P.149) A. BEECH 8. S. 88 E. 16; BEECH 12. N. 36 W. 25.

NO OTHER CORNER HISTORY AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP ON LINE BETWEEN I-11 AND K-11 AND ON OCCUPATION LINE TO NORTH.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 8 July, 96 *BR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP  
-NAIL & TAG IN W SIDE 14" CHERRY N15E 27.24'  
-NAIL & TAG IN E SIDE 16" WALNUT N50W 45.68'  
-NAIL & TAG IN SW SIDE 12" WALNUT N65W 60.92'  
-NAIL & TAG IN NW SIDE 16" WALNUT S45W 35.59'  
-ON OCCUPATION LINE TO NORTH

*Raymond Moored*

Date 12/11/97

Surveyor's Michigan License No. 26463

