

SURVEY & REMONUMENTATION
AUG 22 1995
COMMISSION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 20 10 55 AM '95

Sandy Schondelmarer
REGISTER OF DEEDS

For corners in
BARRY
(County)

Located In: Corner Code #

- 1. Public Land Survey T 4N R8W K-3
- CORNER COMMON TO SECTIONS 1,2,11,&12 CARLTON TOWNSHIP
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

002297

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BRIAN REYNOLDS, in a field survey on 15 APRIL, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830(R8W,P.147)
W. ASH 28 N59W 18 SUGAR 7 S89E 12
NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO PHYSICAL EVIDENCE OF CORNER. COMPUTED POSITION TO BEST HARMONIZE FOUND IRONS AT L-3 AND K-2 WITH 1/4 LINE AND 1/8 LINE OCCUPATION EAST, WEST, AND SOUTH. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
3 May '94
BRIAN REYNOLDS COUNTY SURVEYOR



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A UTILITY POLE S52°W 64.26'
SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 12" ELM S25°E 73.41'
SET 40d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A UTILITY POLE N58°W 58.22'
SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 14" BLACK WALNUT N74°W 114.53'
SOUTHEAST CORNER OF A GARAGE N74°W 212.97'
4'+/- WEST OF THE CENTERLINE OF NORTH-SOUTH GRAVEL ROAD.
4'+/- SOUTH OF THE CENTERLINE OF EAST-WEST BITUMINOUS ROAD.

Signed by [Signature] Date MARCH 17, 1995
 Surveyor's Michigan License No. 31602